

Layton Construction Company, LLC

2020

PROJECT SAFETY MANAGEMENT PLAN



Acknowledge of Receipt and Compliance Agreement



I have received and read the Layton Project Safety Management Plan

I acknowledge that the contents of the PSMP describe Layton's construction practices and safety standards for construction on all Layton projects. The PSMP manual does not contain all OSHA standards, but I agree to comply with Federal OSHA standards, and state and local standards as well as Layton policies outlined in the PSMP. If there is any inconsistency in the foregoing standards, I will comply with the most stringent standard on the applicable subject.

Project Name: _____

Project Location: _____

Company Name: _____

Signature of Principle: _____ Date: _____

Printed Name of signee: _____

PROJECT INFORMATION:

Project Name:

Project Address:

Project Number:

Project Superintendent:

Project Superintendent Phone:

Project Manager:

Project Manager Phone:

Project Safety Manager:

Project Safety Manager Phone:

Scope of Work:



SAFETY DECLARATION

Safety and accident prevention must be a part of all trade contractors bid preparation when choosing to work with Layton Construction. When bids are presented, it is understood that the submitting companies will meet government and Layton standards for safety and accident prevention on all Layton Construction projects, including all safety processes outlined in this declaration. (In the event where the Layton Standard and OSHA requirements are different, the most stringent standard will apply.)

General Minimum Requirements

(Not all-inclusive; refer to 29 CFR 1926 and Layton Site Specific Safety Plan: laytonconstruction.com)

Subcontractor Pre-mobilization

Prior to mobilization, each subcontractor's project management and front-line supervision will attend a pre-mobilization meeting. Subcontractor field supervision will discuss detailed project specific safety hazards and describe how they and their sub-tier subcontractors intend to implement and conform to the Project Safety Management Plan (PSMP).

Daily All Hands Production/Safety Huddle

All hands Layton Construction Project Team led message, warm up/stretching, prime sub activities review, and critical pre-task plan activities discussed.

Subcontractor Supervision and Audit Requirements

Subcontractor onsite supervisor should have OSHA 30 Hour training. A full-time safety professional is required onsite when subcontractors and their tiers reach 50 employees. Subcontractor supervisors will be required to complete a documented weekly safety audit in BIM 360 Field. This audit will list corrective actions taken for hazardous or non-compliant issues found.

Crew Daily Pre-Task Planning

A documented pre-task safety plan will be completed daily by each crew working on LCC projects. Trade front-line supervisors will analyze tasks to be performed by their crews and identify the work sequences, hazards, training, controls and emergency action plans necessary to protect workers.

Weekly Subcontractor Coordination Meeting

Each trade contractor supervisor will be required to attend the weekly coordination meeting where safety concerns, suggestion and planning will take place.

30 Foot LaPSZ (Layton Personal Safety Zone)

The 30-foot LaPSZ (Layton Personal Safety Zone) is the 30-foot area surrounding an individual. It is the obligation and duty of that individual to watch for people, equipment, traffic, or other potential hazards that may occur within their 30-foot LaPSZ and encourage safe work practices from all workers. All employees (including co-worker and subcontractor employees) are responsible to watch for and stop unsafe actions or situations within their 30-foot area of influence, as well as watch for and recognize positive safe actions and situation.





Maximum Lifting Weight for Workers

75 lbs. maximum lifting weight, not to be exceeded without LCC Supervisor approving plan.

Disciplinary Action

A major offense resulting in serious or costly consequences, or repeated minor offenses for which a group or individual shows a lack of responsible effort to correct, may result in suspension or removal. Discipline is intended to preserve good working conditions for all employees and encourage each employee to be responsible and conscientious.

Accident Reporting

All incidents on the project will be reported immediately to the Layton project team, regardless of severity. Post-accident drug testing may be required for everyone involved in the accident. This determination will be made by the Layton Construction project team on a case by case basis.

Personal Protective Equipment

As a minimum, clear eye protection meeting ANSI-Z 87, hard hats meeting ANZI-Z-89, and high visibility vests or shirts meeting class II reflective criteria, shall be worn at all times on the project outside of an office setting or an enclosed cab. Work gloves - appropriate for the task - shall be available and used where required.

Housekeeping

All subcontractors will practice good housekeeping such that related hazards are eliminated. Trash and debris are to be removed to dumpsters each shift. Cords and hoses are to be elevated, bridged, buried or controlled to eliminate trip hazard and damage from equipment travel. Work areas will be kept organized and free of clutter. Walkways and stairs will be kept clean and free of construction materials.

Fall Protection

All subcontractors will follow the Layton Ladders Last program, including Ladder Permit and Ladder Tag process. When exposed to a fall of 6 foot or greater, fall protection must be used. When engineering controls do not fully mitigate the fall hazard, 100% tie-off is required using a full-body harness fully compliant with OSHA 1926 subpart M. Shock absorbing lanyards are prohibited, self-retracting deceleration devices (yoyos) are preferred.

Equipment Operation

Equipment operators must be able to show proof of training All equipment is to be operated and maintained as per manufacturers recommendations.



Signature CEO/Principal Date

Company Name Title

ENVIRONMENTAL SAFETY AND HEALTH COMMITMENT

At Layton Construction, the commitment to Environmental, Safety and Health is an extension of our philosophy of Constructing with Integrity.

Our commitment to Safety excellence is emphasized by:

- *Management's commitment and accountability to provide a safe and healthy work environment*
- *Encouraging open communication between all project personnel and soliciting input, support and action to achieve an injury-free environment*
- *Providing training and equipment to help ensure employee safety and project success*
- *Promoting safety as a value rather than a directive and extending that value into all areas of our lives*

At the Layton Companies, Environmental, Safety and Health are everyone's responsibility. As a condition of employment with Layton Construction, all employees are accountable to adopt safety as a value and comply with the Best Practices of the highest level of Environmental, Safety and Health Standards and Guidelines.



TABLE OF CONTENTS

LAYTON CONSTRUCTION STANDARDS OF SAFETY	9
Layton Injury Free Environment - L.I.F.E.	9
Responsibility and Accountability	9
Orientation, Training and Meetings	11
LaPSZ – Layton Personal Safety Zone	13
Safety Regulations	14
Monthly Inspection Procedures	14
Notification of Unsafe or Hazardous Conditions.....	15
Disciplinary Program	15
Daily / Weekly Inspections	16
Subcontractor General & Project Specific Requirements	16
CRISIS AND EMERGENCY PREPAREDNESS PLAN	18
LAYTON CONSTRUCTION SAFETY POLICIES	22
Incident and Injury Management and Reporting Policy.....	22
Incident Investigation	24
Return to Work Policy – Light Duty Policy.....	25
Substance Abuse Policy	25
Tobacco Policy	26
Cell Phone Use Policy on Layton Construction Projects.....	26
Personal Protective Equipment (PPE)	27
Sanitation.....	28
Heat Illness Prevention.....	28
Daily Huddle and Stretch and Flex	29
Maximum Lifting Policy	29
Utility Protection Policy.....	29
Environmental Policy	30
Air Pollution Control Plan	30
Hazard Communication	31
LAYTON CONSTRUCTION SITE SPECIFIC STANDARDS.....	32
Asbestos Procedures/Processes.....	32
Lead	32
Silica.....	32
Concrete Construction.....	33
Precast Concrete	33
Confined Space	34
Mobile Elevated Work Platforms (MEWPs).....	34
Crane Safety	35
Rigging	38
Demolition	38
Electrical	38
Lock Out/ Tag Out.....	39
Equipment and Vehicles	41
Excavation and Trenching.....	41
Fall Prevention/Protection	41
Fire Protection Prevention	42
Hand and Power Tools.....	43
Hot Work Operations	44
Housekeeping.....	45
Ladders and Stairways.....	45
Lasers.....	46

Maintenance and Protection of Traffic	46
Masonry Construction	46
Scaffolding	46
Steel Erection.....	47
Temporary Barricades	47
Tilt Up Panel Construction Procedure	48
Tilt Up Panel Erection Procedure	48
Welding and Cutting.....	50
FORMS APPENDIX.....	51
Employee Incident Report.....	52
Supervisor Incident Report.....	53
Witness Statement Report	54
Competent Person Form	55
Confined Space Entry Permit.....	56
Daily Pre-Task Plan	57
Energized Work Permit.....	59
Excavation Permit.....	60
Guardrail Removal Permit	61
Harness and Lanyard Inspection	62
Hot Work Permit.....	63
Critical Lift Plan.....	64
Lock Out / Tag Out Checklist	66
Monthly Inspection Color Codes Sign.....	68
Notice to Commence Steel Erection	69
Pre-Mobilization Meeting Agenda	70
Scaffold Tags - Red.....	71
Scaffold Tags - Yellow	72
Scaffold Tags - Green.....	73
Silica – Table 1	74
Utility Protection Permit.....	76
Notice of Non-Compliance	77

LAYTON CONSTRUCTION STANDARDS OF SAFETY

The purpose of Layton Construction's safety standards is to assist project management, subcontractors, and field employees in understanding Layton Construction's Injury Free Environment (L.I.F.E.) philosophy and the health and safety expectations and requirements for its projects. The standards of safety within this document represent the expectation of performance on EVERY Layton Construction project.

LAYTON INJURY FREE ENVIRONMENT - L.I.F.E.

Layton Construction is committed to an "Injury Free" environment. L.I.F.E. is the shared corporate and individual belief that safety is a value not compromised by cost or schedule. Everyone has the right to go home safely at the end of the day.

Layton Injury Free Environment (L.I.F.E.) holds three basic premises:

- All incidents and injuries are preventable – no level of incident or injury is acceptable
- Injury Free operations are possible in construction – if a prevailing mindset and conviction exists to do the right thing and to do what is necessary to achieve that state
- Elevate safety awareness daily – a journey of continuous improvement to advance safety and achieve a heightened state of awareness where field employees are responsible and accountable for their own safety and the safety of their co-workers

An injury free environment includes a willingness to adapt to any new safety initiatives implemented during construction by the Layton Construction project team emphasizing the continual improvement process to protecting field employees.

RESPONSIBILITY AND ACCOUNTABILITY

Everyone associated with the project must understand his or her responsibilities concerning health and safety on the project. With the responsibilities defined, project management, supervision, subcontractors and craft workers will be held accountable for their health and safety performance.

Project Management includes: Project Executive, Project Director, Project Manager, Project Superintendent, Project Engineer, and ESH Vice President.

Front-line Supervision includes: General Superintendents, Superintendents, Field Engineers, General Foremen, and Foremen. The matrix below serves to associate tasks with positions(s) responsible.

Subject	Project Management Will Ensure That:	Front-Line Supervision Will Ensure That:	Craft Employee Will:	Subcontractor Site-Safety Representative Will:
Project Management Plan	All project team members will participate in preparing the PMP.	Aspects of the PMP pertaining to safety will be communicated in site orientations to the craft workers.	All craftsmen must be aware that they will be required to participate in site specific orientation.	Safety Manager will support the team in preparing the PMP and point out safety hazards and how to mitigate them.
Project Safety Management Plan (PSMP):	The PSMP is understood, implemented, and complied with by Layton Construction, subcontractors, vendors, or third-parties working or visiting the project.	The PSMP is fully understood, implemented in work planning and communicated to craft workers. The project is compliant with all aspects of the PSMP.	Understand the contents of the PSMP and follow the established rules, procedures, and safety initiatives.	Understand the contents of the PSMP and follow the established rules, procedures, and initiatives.

Subject	Project Management Will Ensure That:	Front-Line Supervision Will Ensure That:	Craft Employee Will:	Subcontractor Site-Safety Representative Will:
Work Practices:	Front-line supervision is communicating safe work practices to all craft workers.	All work tasks and expectations are properly communicated to craft workers and that all craft understand and comply.	Follow all safe work practices and expectations as communicated to them by their supervisor.	Ensure project is compliant with safe work practices and federal, state, local, and company regulations, rules, and procedures.
Site-Specific Safety Rules:	The site-specific safety rules and procedures are implemented and enforced.	The site-specific safety rules and procedures are understood, communicated, and implemented.	Understand and follow the site-specific safety rules, procedures, and initiatives.	Assess project conformance to site-specific safety rules and procedures. Documented in BIM360 Field as issues.
Orientation:	Resources are available to conduct a proper site-specific orientation. They will participate in the orientation process.	They will participate in the orientation process.	Attend orientation <u>prior</u> to beginning work. Understand and follow the site-specific safety rules and procedures covered in the orientation.	Support project management team and front-line supervision in the implementation of the policies, procedures, and initiatives covered in the orientation.
Training:	Resources are available to implement health and safety training. Training programs are developed and implemented.	They must attend the Pre-Mobilization meeting prior to start of work. All craft workers under their direction are properly trained in hazard recognition and safe work practices.	Attend all required project health and safety training. Understand and follow the work practices and guidelines discussed during training.	Ensure that project management team, front-line supervision, and craft have received proper health and safety training. Assist project supervision in training craft on hazard recognition and safe work practices.
Safety Planning	Prequalification system is utilized for contractor selection. All front-line supervision identifies, evaluates, and controls the project site hazards, and provides resources to implement controls.	All hazards are identified, evaluated, controlled, and addressed in Daily Pre-Task Plans. Complete daily BIM360 Field safety checklists to identify, evaluate, and correct work site hazards.	Understand the hazards of the work and follow the safe work practices and controls developed for those hazards.	Assist in evaluating hazards and determining methods of eliminating or reducing the hazard. Site supervisor will complete weekly BIM360 Field safety checklists

Subject	Project Management Will Ensure That:	Front-Line Supervision Will Ensure That:	Craft Employee Will:	Subcontractor Site-Safety Representative Will:
Incidents:	All incidents are investigated properly and thoroughly. Must report the incident the same day of occurrence. A Root Cause Analysis should be completed within 72 hours of the incident.	They conduct a thorough and proper incident investigation and develop solutions from that investigation.	Participate in the incident investigation process and contribute ideas and solutions.	Assist front-line supervision in investigating all incidents.

ORIENTATION, TRAINING AND MEETINGS

To promote and ensure a Layton Injury Free Environment, health and safety training is a requirement for all Layton Construction and subcontractor craft workers assigned to the project.

Foreman/Front-line Supervisor - Pre-Mobilization Meeting

All front-line supervisors are required to attend a Pre-Mobilization meeting prior to the mobilization of their crew so that they can receive site-specific training and review permits, forms, procedures, and safety initiatives required by the project. In this meeting the team will discuss site specific information necessary to adequately coordinate work and prepare crews to adequately complete the scope of work. The Pre-Mobilization meeting agenda is located in Appendix 14.

OSHA 30 Hour Training

It is preferred that the lead subcontractor supervisor on site has completed the OSHA 30 Hour outreach training and provide documentation of completion at the Pre-Mobilization meeting prior to start of work.

Employee Site Specific Orientation

All craft workers will attend an environmental, safety, and health orientation **prior** to starting any work on the project. The Layton safety orientation will provide general health and safety information, project specific work rules, and procedures. Upon completion of training, each person will receive a sticker for their hardhat.

Daily Huddles

All craft workers on a project will participate in a daily pre-shift production and safety coordination huddle conducted by Layton Construction supervision. Layton Construction reserves the right to remove any subcontractor management and/or supervision personnel that do not regularly attend the daily huddle. Subcontractor supervision will document weekly safety meetings and inspections in BIM360 Field. Safety meetings should communicate safety concerns, new work activities, new and continuing potential hazards, and any incidents that have occurred on the project as well as corrective actions taken.

Health and Safety Training

In addition to site-specific safety and health orientation, OSHA requires that craft workers receive specific task training. To help comply with OSHA minimum worker training requirements and assist in achieving an injury-free workplace, a training matrix has been included to assist in the identification of applicable training requirements. Layton Construction may evaluate orientations and training periodically to verify they are being properly conducted and that the contents adequately cover the standards, policies, rules, procedures, and initiatives contained in the PSMP or OSHA standards. Project management or supervision will communicate the safety and health policies, rules, procedures, and initiatives to all vendors and third-party individuals visiting the project.

TOPIC	WHO NEEDS TRAINING	WHAT TRAINING IS NEEDED
30 Hour OSHA	One Supervisor minimum trained	30 Hour OSHA training by accredited outreach program

TOPIC	WHO NEEDS TRAINING	WHAT TRAINING IS NEEDED
Project Specific Safety Orientation	All project management, supervision, and craft workers entering the project.	Safety rules and procedures contained in the PSMP's site-specific emergency action plan, each worker's responsibilities, disciplinary program, and stretch and flex.
Hazard Communication	All craft workers entering the project	Hazard Communication Basic Training (see Haz-Com section in the PSMP)
Respiratory Protection	Workers required to wear respiratory protection, including dust masks	OSHA 29 CFR 1910.134 & 139 or 1926.103
Fall Protection	Any craft worker who might be exposed to a fall hazard	<ul style="list-style-type: none"> • The nature of fall hazards • Fall protection standards • Procedures for erecting, disassembling, maintaining and inspecting fall protection systems • Use and operation of: guardrail systems, personal fall arrest systems, safety net systems, warning lines, safety monitoring, controlled access zones, and other protection when used • Procedures for handling equipment and erection of overhead protection
PPE	All Workers using PPE	Refer to the section on PPE in this PSMP or the OSHA regulatory standards
Forklifts	Operators of powered industrial trucks	<ul style="list-style-type: none"> • Types of trucks operated • Hazards of the workplace • Hands-on performance evaluation • Re-training every 3 years to maintain compliance
Confined Spaces	Any worker attending to, supervising, entering, or working within a confined space	<ul style="list-style-type: none"> • Hazards of the space • Duties of entrants • Air monitoring
Permit-Required Confined Spaces	Any worker attending to, supervising, entering, or working within a confined space	<ul style="list-style-type: none"> • Hazards of the space • Duties of entrants, attendants, supervisors • Measures used to eliminate or control hazards • Air monitoring requirements • Emergency procedures/rescue equipment • Communications • Permitting procedure • PPE
Excavation / Trenches	Workers entering or working within an excavation / trench	<ul style="list-style-type: none"> • Hazards of the space (slides, cave-ins, water accumulation, etc.) • Safe means of access/egress • Proper support system procedures (erection, maintenance, disassembly, and inspection)
Lockout / Tagout	Workers affected by hazardous energy sources	<ul style="list-style-type: none"> • Nature of known hazardous energy sources • Project-specific Lockout/Tagout procedures
Gas Welding, Arc Welding & Cutting	Workers conducting gas welding and/or cutting	<ul style="list-style-type: none"> • The safe use of fuel gas systems • What to do with unattended machines and electrode holders • Operations around water, and in damp or humid conditions • Shield arc welding
Hot Work with Combustibles, Flammables	Workers conducting hot work activities such as cutting, welding, brazing, or grinding	<ul style="list-style-type: none"> • Hazards of the area • Permits • Duties of Fire Watch

TOPIC	WHO NEEDS TRAINING	WHAT TRAINING IS NEEDED
		<ul style="list-style-type: none"> • How to use a fire extinguisher
Scaffolding	Workers working from scaffolding	<ul style="list-style-type: none"> • The nature of any known hazards • Proper erection, maintenance, and disassembly of fall protection systems • Electrical hazards in area • Falling object protection • Material/equipment handling from scaffold • Maximum load-carrying capacity • Scaffold tagging system • Access and egress
Crane Baskets	Workers working from crane baskets	<ul style="list-style-type: none"> • Safe work rules • 100% fall protection • Lift plans contents • Emergency procedures
MEWP (Mobile Elevated Work Platform)	Workers in scissor lifts and articulating boom lifts	<ul style="list-style-type: none"> • Safe work rules • 100% fall protection • Emergency procedures

LAPSZ – LAYTON PERSONAL SAFETY ZONE

The 30-foot LaPSZ (Layton Personal Safety Zone) is the 30-foot area surrounding an individual, 15 feet in all directions. It is the obligation and duty of each individual to watch for people, equipment, traffic, or other potential hazards within their 30-foot LaPSZ and encourage safe work practices from all craft workers in the 30-foot area. “Being our brother’s keeper” is a concept that is paramount to the success of the 30-foot LaPSZ. All employees including co-workers, subcontractor employees, vendors, and owners are responsible to watch for and stop unsafe actions or situations within their 30-foot zone. It is also important to watch for and proactively commend safe actions and situations as they are observed to create a positive safety culture on each Layton Construction project. If a hazard is noticed in the 30-foot LaPSZ, immediate action should be taken to correct the unsafe situation, including a report of the concern to a supervisor. These observations can also be documented in BIM360 Field as Safety Conforming or Non-Conforming issues. Although an individual may not be able to see what activities are underway above or below deck floors in their 30-foot LaPSZ, questions must be asked to learn of any changing conditions that may occur affecting the work environment above or below.

Hazard Recognition

They key to the 30-foot LaPSZ program is hazard recognition. Each person needs to be aware of the activity and people in their line of sight and to draw upon safety training and work experience to act when they notice a potential hazard. Hazards recognized and acted upon by anyone can also be documented in BIM360 Field as a Safety Non-Conforming issue. When a hazard is recognized, the deficiency should be pointed out respectfully. They should first **remind** the person of the hazard, safety policy, standard, or initiative; then **request** the cooperation and compliance; and if necessary, **report** the situation to a supervisor if unresolved.

Accountability

Layton Construction has invested a great deal of time and resources to encourage employee safety. Accountability for all workers on Layton Construction projects includes the following safety expectations and consequences:

- Workers are empowered and expected to correct hazards and safety violations in their 30-foot work area
- There are no exceptions! Employees at all levels are expected to participate in LaPSZ
- If an incident occurs within a worker’s 30-foot area of responsibility the worker will be asked to participate in the incident review process
- Workers who do not follow the Layton Construction safety policies, procedures, and initiatives will be disciplined, including possible removal from the project
- Every individual is entitled to work in a safe environment. Each employer and employee are asked to adopt the 30-foot Layton Personal Safety Zone (LaPSZ) and do everything in their power to protect themselves and others

SAFETY REGULATIONS

Layton Construction and subcontractors will comply with all applicable government regulations, specific client policies and regulations, and this PSMP. If any of these standards, requirements, rules, procedures, or initiatives conflict, the most stringent one will prevail.

MONTHLY INSPECTION PROCEDURES

Monthly inspections involve items that are to be inspected monthly by a designated Competent Person.

Definition of a Competent Person: A person capable of identifying existing and predictable hazards and who has the authority to take prompt corrective measures to eliminate the hazards and remove individuals that are in danger.

Equipment requiring monthly inspection includes:

- Personal fall protection and fall arrest systems
- Electrical cords and power tools
- Ladders
- Fire extinguishers
- Rigging

General Guidelines:

The name of the Competent Person will be documented and published to all employees; any employee who falsifies a monthly inspection result will be disciplined up to and including termination. The color code of the month will be mentioned at the weekly tool box safety meetings.

Safety Color Code of the Month (see Appendix 12)

January and July	Yellow
February and August	White
March and September	Brown
April and October	Green
May and November	Red
June and December	Blue

Personal Fall Protection

All fall protection equipment will be inspected before each use as per the OSHA standard 1926.502(d)(21). Monthly inspection of fall protection: body harnesses, lanyards, and wall chains will be inspected for cuts, tears, abrasions, worn stitching, cracks, burns, and freely moving parts. No alterations are allowed and each item will include correct labeling from the manufacturer. All personal fall protection that is damaged will be removed from service, destroyed, or sent to the manufacturer for repair. The monthly color code tape will be visibly placed on the fall arrest equipment. All inspections of fall protection must be completed in writing each week.

Electrical Cords and Power Tools

Any employee using electrical equipment and/or cords will perform a pre-use visual inspection of each cord set, plug, receptacle, spider box, temporary power panel, and tool or equipment connected by cord and plug with periodic inspections documented monthly. Any possible hazards, damage, or missing parts that pose a hazard will be reported and the equipment removed from service, repaired, or destroyed. A tag will be placed on the item stating: “**Caution Do Not Use**” per the OSHA standard 1910.334(a)(2)(i). The Competent Person will perform the following test on GFCIs (ground fault circuit interrupter) and equipment identified above. These tests will be performed and documented monthly.

- Continuity
- Polarity
- Ground continuity
- GFCIs will be tested with an approved trip tester
- Double insulated equipment will be inspected for damages
- The monthly color code tape will be placed on the male and female end of the extension cord or power tool to ensure the entire length has been inspected

Ladders

The employee using the ladder will perform a daily visual inspection and sign the ladder tag affixed to the ladder. Any damaged ladder will be removed from service and tagged: **"Caution: Do Not Use."** A monthly inspection by a Competent Person is required per the OSHA standard 1926.1053(b)(15). Bends, dents, cracks, loose or missing rivets, disconnected braces, and corrosion can weaken a ladder. Carefully inspect the area around rivet points on fiberglass ladders for hairline stress cracks. Destroy any defective ladders immediately and remove them from the site. The monthly color code tape will be placed on the right-side rail at eye level between 5 and 6 feet high.

Fire Extinguishers

Fire extinguishers will be inspected monthly as per the OSHA standard 1926.150(a)(4). This will ensure that the fire extinguisher is ready in case of need. Check that the extinguisher is charged by looking at the green arrow on the pressure indicator to insure it is in the green section:

- Be sure the lock pin is firmly in place
- Keep the extinguisher clean
- Check for dents, scratches, corrosion, or any other damage
- Check the discharge nozzle; make sure it is clean and free of debris
- Tip fire extinguisher upside down and lightly tap bottom with a rubber mallet
- Fire extinguishers will be placed within 100 Feet of a Class A fire hazard and near stairways on a project
- Check for the annual state inspection tag

Fire extinguishers that do not meet the criteria above need to be taken out of service and repaired, recharged, or removed from site. The monthly color code tape will be placed on the hose of the extinguisher as close to the handle as possible.

Rigging

All rigging will be inspected prior to each use and or monthly, whichever comes first per OSHA standard 1926.251(a)(1). Damaged or defective rigging will immediately be removed from service and either repaired or destroyed. All rigging (chains, wire rope chokers, synthetic webbing) must have a manufacturers identification tag stating the name or trademark of the manufacturer, the size and rated capacity, and the type of material. This identification tag **MUST BE LEGIBLE**. The monthly color code tape will be placed on the end of the rigging below the identification tag. All documented inspections will be completed the first week of every month. All existing color code tape will be removed each July and January (at minimum).

Type of Rigging	Inspections will include:
Wire Rope	Look for evidence of heat damage, broken wires (10 in one lay or 5 in one strand) of a lay, kinking, smashing, corrosion, bird caging, distorted rope structure, or damage to attachment points.
Natural Rope and Synthetic Fiber Slings	Look for abnormal wear, powder between strands, broken or cut fibers, variation in the size or roundness of strands, discoloration or rotting, or distortion of hardware in the sling.
Synthetic Webbing	Look for acid and caustic burns, melting or charring of any part of the sling surface, snags, punctures, tears or cuts, distortion of fittings or broken or worn stitching.
Hooks	Look for distortion such as bending, twisting, or increased throat openings, wear, cracks, nicks, or gouges, damaged or malfunctioning latch engagement, as well as damaged or malfunctioning hook attachment.

NOTIFICATION OF UNSAFE OR HAZARDOUS CONDITIONS

Each person on a Layton Construction project has the right and responsibility to notify project management or supervision of any unsafe or hazardous condition that may be present without fear of retribution. Project management or supervision will take immediate action to correct or remove any hazards brought to their attention.

DISCIPLINARY PROGRAM

At-risk behavior on the project will not be tolerated. Each person has a responsibility to work safely and front-line supervisors are responsible to correct at-risk behavior of employees under their direction. If you see something that does not look right, stop and follow the LaPSZ procedure, or report it to your supervisor. Discipline is intended to preserve safe

conditions for all employees and encourage individuals to be responsible. Disciplinary action may include verbal warnings, written warnings, and removal from the project (days without pay). For minor offenses, the employee will be expected to agree to improve behavior. These minor offenses, if not corrected may later be recorded as a written warning. Suspension or discharge will result from major offenses, those with serious or costly consequences, or for repeated minor offenses for which an employee shows lack of effort to correct deficiencies. Examples of major offenses are those related to fall protection, confined space, red-barricaded space, electrical or lockout/tagout violations, or disregarding specific instructions that resulted in an on-site incident (including property damage, injury, or a near miss event).

DAILY / WEEKLY INSPECTIONS

Layton Construction and all subcontractors will perform safety and quality inspections of their scope of work. All subcontractors will be required to purchase and utilize an iPad (IOS device) on-site. The checklist and reporting tools presented in BIM360 Field will serve as the only acceptable method to record these safety and quality inspections. These required checklists include: Daily Pre-Task Plans, Weekly Safety Inspections, Weekly Safety Meetings (all found in the task tab). Other checklists related to QA/QC and safety based on scope of work will also be assigned through the task tab. Subcontractors working on a Safety CAP will additionally be required to complete the weekly Safety CAP Compliance checklist. Issues related to Safety and QA/QC will be assigned to subcontractors as needed; these issues need to be rectified and marked as “work complete” so that the Layton project team can close the issue following inspection.

Daily Pre-Task Planning

A Daily Pre-Task Safety Plan will be completed daily by each crew performing work on the project. Daily Pre-Task Planning will be completed in the field, in the location that the crew will perform the scope of work, and with participation from the entire crew. Layton Construction and all sub-contractors are required to use the Daily Pre-Task Plan checklist in BIM360 Field or a paper form (see Appendix 4). Each front-line supervisor with input from the crew will analyze the tasks identify the work sequence, possible hazards, training requirements, necessary controls, and emergency action plans needed to protect workers from any identified hazards. The day’s work will be broken down into individual steps including known hazards associated with each step and how to mitigate that hazard. All craft workers will sign the plan signifying that they understand the work activities, hazards, and controls.

The completed Pre-Task Plan will remain visibly located near the work activity for review throughout the day. After completion it will be uploaded into BIM360 Field as an attachment for documentation purposes.

Accountability: Plan-Do-Check-Act

The intent of the Daily Pre-Task Plan is to ensure crafts are prepared to anticipate hazards and adopt safe means and methods to accomplish each task safely. Accountability for the pre-task planning process includes four key components:

- Plan – The crew lead or foreman is accountable for leading his crew to identify hazards and develop mitigation methods
- Do – The crew lead and craft are accountable for following the plan
- Check – Supervision is responsible to spot check the process, both the quality of the plan and the rigor of compliance
- Act – All members are accountable to identify unforeseen conditions and to act to improve the plan and mitigate the hazard

SUBCONTRACTOR GENERAL & PROJECT SPECIFIC REQUIREMENTS

Subcontractors must demonstrate safety knowledge relevant to 29 CFR 1926 OSHA Construction Standards. Subcontractors will be required to provide current certificates of their project supervisor’s safety competency in the form of: 30-Hour OSHA, Safety Trained Supervisor (STS) through the Board of Certified Safety Professionals (BCSP), Construction Site Safety Supervisor Certification through National Center for Construction Education and Research (NCCER), or equivalent. This documentation is to be attached to the Competent Person Form required with submittals, as well as during the Pre-Mobilization Meeting (in case supervision changes between pre-award and start of project). If any supervisor changes are made following mobilization, certifications will be provided immediately to Layton Construction.

Each subcontractor will designate a safety representative prior to mobilization. The on-site safety representative will be a Competent Person who has completed at minimum 10 hours of OSHA awareness training, and who may have other on-site duties. Subcontractors that have 50 or more workers (including tiered subcontractors) will provide a **full-time on-site** safety professional upon mobilization, this person will have no other on-site responsibilities. Layton Construction management reserves the right to require a full-time on-site safety professional any time. Subcontractors will submit the resume of the proposed safety professional or representative to be reviewed by Layton Construction project team at pre-mobilization. Layton Construction will determine if the proposed safety professional or safety representative has the required training and experience required for the specific project. Subcontractor safety representative will have full authority to implement safety corrections and recommendations. The safety supervisor/representative will have the authority and responsibility to ensure the proper implementation of this PSMP. Subcontractor safety representatives will have authority to stop any work they deem unsafe.

Subcontractor full-time on-site safety professionals will have the following **minimum** qualifications:

- Five year's construction experience, one year of which includes on-site construction safety responsibilities
- Specialized training relevant to scope of work
- OSHA 30-hour construction safety awareness course
- Working knowledge of safety regulations and hazard control methods
- Demonstrated ability to conduct safety training


The minimum duties of designated safety professional and/or representative will be:

- Investigate any incidents or near miss and report the findings to Layton Construction
- Attend safety meetings as required by Layton Construction
- Conduct regular safety meetings with craft to instruct them on project safety practices and requirements
- Conduct written daily safety inspections of work activities and document them in BIM360 Field through either checklists or issues (both conforming and non-conforming) to ensure compliance with safe work practices and this PSMP
- Take direction from Layton Construction related to timely abatement and control of hazards

CRISIS AND EMERGENCY PREPAREDNESS PLAN

It is expected that every Layton project have an established and rehearsed plan of response to an emergency or crisis condition. The intent of this section is to provide guidance as to what information is needed such that a consistent response can be expected.

CRISIS MANAGEMENT TEAM ORGANIZATION



General Response Procedure

Site Management will establish and train site personnel regarding emergency response procedures.

Site Management will maintain, as necessary, emergency response supplies and equipment to meet emergency response needs.

Layton Construction supervisors will notify emergency response personnel of emergencies at the project site.

The appropriate supervisor or responding personnel will initiate the notification process, which includes alerting local response organizations (such as ambulance or fire personnel) and/or others as required.

Notify the following immediately:

- Project Manager
- Project Superintendent
- Project Safety Manager
- ESH VP
- SBU Executive Vice President
- Director of Corporate Communications/Company Spokesperson

****Layton Construction Management (ESH VP and SBU EVP) must be called as soon as possible****

If necessary, the Project Superintendent will coordinate with local emergency organizations and provide the following:

- Technical information about hazardous materials and products
- Quantity and/or size of hazardous materials or products
- Locations and methods of storage for hazardous materials or products
- Report known hazards of materials or products
- Provide a copy of the Safety Data Sheet (SDS)

Layton Construction site management will make site equipment and supplies available until the emergency has been resolved.

First Hour Response: Site Superintendent Checklist

- Contact emergency services (911)
- Contact Project Safety Manager

- Account for all employees
- Project Safety Manager to contact Regional Safety Manager and ESH VP (if needed)
- Notify the SBU Executive Vice President
- Do not move potential evidence
- Direct all outside inquiries to company Spokesperson
- Post people to restrict entry to site or direct emergency response teams
- Notify owner/developer (varies by project)

Site Actions – General Response Procedures

- Ensure the scene is safe before entering the area
- Review site for hazards. Isolate hazardous area(s)
- Secure the site from further hazards (i.e. turn off utilities, remove hazardous substances not involved, stop flows of product or water, etc.)
- Attend to the injured, render first aid
- Call 911 or facility emergency number. Give the following information:
 - Name of person reporting the emergency
 - Nature and severity of the injury or illness
 - Locations and phone extension from which they are calling
 - Number of people involved
 - Directions to the site of the emergency
- Secure and isolate incident site. Do not move anything that does not have to be moved, only things to assist the injured or make the area safe. Make note of those items that must be moved. For major incidents, site emergency shutdown is required
- Take a roll call. Account for each site employee, vendor, owner's rep, and trade contractor employees
- Keep only those on-site who are essential in the recovery process. Release those who are not needed and require them to leave the site
- Establish first aid and evacuation areas, if needed, where ambulance or air evacuation services have access
- Control site access
- Start investigation and reporting procedures

First Hour Response: Business Unit Executive VP

- Contacted by the Site Superintendent
- Determine what/where/when the event happened and who is involved
- Verify current status of site operations or shutdown
- Notify Dave Layton
- Notify Corporate Spokesperson
- Advise project assistant and receptionists where to route calls
- Notify VP Chief Human Resource Officer

Emergency Preparedness Training

Employees and subcontractor management and employees will be trained on the subjects below as appropriate:

- Emergency notification and reporting procedures
- Site emergency and evacuation procedures
- Points of assembly
- A site map will be posted for all contractor and subcontractor employees, showing the points of assembly locations

Crisis Communications Plan (Media Requests)

If contacted by the news media concerning an incident, be supportive. However, communications must be coordinated effectively.

- Designate a single company spokesperson (Vice President of Marketing and Communications, unless assigned to someone else on the job site due to a remote location or other circumstances). Refer media calls immediately to the company spokesperson
 - Designated Spokesperson: _____
- Establish a controlled access site for media at a safe distance from the incident to maintain scene safety and coordination (at a distance from the scene, jobsite management trailers and employee jobsite gates)
 - Gathering Location: _____
- The company spokesperson and project management team will develop an initial statement of known information that can be provided as soon as possible
- Provide regular updated information as it becomes available
- Create a log of persons from the media including organization, phone numbers, and email addresses for effective continued communication
- Project Management and site employees should not engage in social media activity regarding the incident. Unauthorized posting to social media about an incident is subject to disciplinary action up to and including termination of employment.

Emergency Action Plan

Project Management will ensure the Emergency Action Plan is communicated to all workers during orientation. Specific emergency procedures and emergency phone numbers will be posted in lunch areas, near all telephones and on all project bulletin boards. The plan will be reviewed periodically by Layton Construction to ensure continued accuracy and applicability. Daily Pre-Task Plans will also address emergency plans.

THIS PLAN WILL BE REVIEWED BY ALL WORKERS AND POSTED WITH A SITE PLAN IN PROMINENT LOCATIONS ACCESSIBLE TO ALL.

PROJECT NAME: _____

WORK LOCATION: _____

This is a project specific Emergency Action Plan communicating evacuation procedures, specific alarms, and assembly points, should an emergency evacuation become necessary because of severe weather, fire, hazardous chemical release, explosion or other emergencies that could cause harm.

It is each person's responsibility to familiarize themselves with evacuation routes, alarms, and assembly points in case an emergency evacuation of the work area is required. **Caution:** Evacuation routes, alarms, or assembly points may differ from one emergency to another. The implementation of a successful emergency response depends on thoughtful planning, training, and execution.

Evacuation

- Exit signs will be conspicuously posted along evacuation routes
- A signal or alarm will be designated to initiate evacuation
- Personnel should de-energize tools and equipment and check the work area for fellow workers in need of assistance.
- Evaluate stairs for safe passage before accessing
- Report any hazardous conditions that are known to exist within the building to your supervisor
- A site plan drawing will be developed for each project's evacuation plan. The drawing will clearly identify the following:
 - Building footprint
 - Primary and secondary assembly area points
 - Exits
 - Fire alarm pull stations or air horn locations
 - Site telephones
 - Stairs
 - Fire extinguishers

- Layton Construction's project office
- First aid kit locations
- Emergency numbers

Medical Emergency

During the safety orientation, workers will be given information on how to summon medical assistance in case of a medical emergency. Everyone should know the following information:

Emergency Phone Number: 911

Project Address: _____

When reporting a medical emergency, the person will state their name, the nature of the emergency, the severity of the emergency, and where assistance is needed. Someone may be required to meet medical personnel and guide them to where the emergency is located.

Do NOT MOVE AN INJURED WORKER BEFORE MEDICAL ASSISTANCE ARRIVES UNLESS FURTHER INJURY IS POSSIBLE.

Fire

In case of fire, evacuate the work area immediately and report to the pre-determined assembly point.

In case of Fire or Emergency:

Emergency Phone Number: 911

Alarm or Notification: Site Specific: _____

Evacuation Route: Out the ground floor exit areas to upwind assembly points

Primary Assembly Point A Is located at _____

Primary Assembly Point B Is located at _____

Utility Shutdown:

Gas (if applicable) Responsible Person: _____

Electricity (if applicable) Responsible Person: _____

Severe Weather

Should weather conditions such as severe thunderstorms or tornadoes develop around or near the project, follow the direction of the immediate supervisor. Projects in areas where severe weather events are possible will have a contingency plan in place.

Chemical Release or Explosion

Workers will immediately evacuate their work area upon hearing the alarm or being notified of the emergency and ordered to evacuate. No employee is exempt from evacuation even if the evacuation is a drill. Everyone is required to report immediately to their designated assembly point and be accounted for. Failure to report may endanger others if they have to search for you. Do not leave the project without prior authorization from front-line supervision.

A Layton Construction employee will contact an identified remediation company to respond to chemical spills that require expert attention. The company will be identified in the PMP.

LAYTON CONSTRUCTION SAFETY POLICIES

The purpose of Layton construction's safety policies is to assist project management, supervision, subcontractors, and craft to understand Layton Construction's Injury Free Environment philosophy and the health and safety expectations and requirements for its projects. The safety policies within this document represent the expectation of performance at EVERY Layton Construction Project.

INCIDENT AND INJURY MANAGEMENT AND REPORTING POLICY

In order to control and manage any incident on a Layton Construction project the following measures will be followed. Each project will have Layton Construction and subcontractor personnel on-site during all work activities that are trained in First Aid and Cardiovascular Pulmonary Resuscitation (CPR).

An **Incident** is defined as any unplanned or undesired event that results in a work-related injury/illness, property damage, or disruption of business.

A **near-miss** is any situation that has the potential under slightly different circumstances, to result in a work-related injury/illness, property damage, serious environmental impact, or disruption of business.

Every incident will be reported immediately to the Layton Construction project team, which will immediately notify the Layton Construction ESH Department. Layton Construction Supervision will take control of the administrative management of the incident and thoroughly investigate to determine the probable root cause. Layton Construction and applicable subcontractor front-line supervision will be involved in the investigation process. The Layton ESH claims specialist must be notified within 24 hours of any injury that occurs on ANY Layton Construction project site. Layton Construction reserves the right to appoint a supervisor from the subcontractor to keep track of the injured person until a full release to work can be obtained. Training will be completed with this supervisor, and a Layton Construction contact will be given to so that a close working relationship can be established to ensure that all the needs of the injured employee are met, as well as the needs of the injury management program. All employees working on Layton Construction projects will follow the Return to Work Policy in this manual, each subcontractor will be responsible to ensure that employees comply with this Return to Work Policy. Light duty is a mandatory requirement on each project to help in the quick recovery of the employee. Subcontractors will establish their own Light Duty Program, or ask how to use light duty on-site.

Site Control Following an Incident

Following an incident, if necessary, administer first aid until help arrives. If the injury is significant and 911 has been called, place employees strategically to direct the emergency response team to the incident scene. For emergencies requiring evacuation, each project will develop a site-specific Crisis Management Plan (see pg. 19). Once the incident is under control, and if necessary, all injured parties are treated and/or transported to a local treatment facility, the investigation team will perform an investigation. The team will consist of the Project Manager as the team leader, the Project Superintendent, Foreman, Project Safety Manager, and any others deemed necessary.


Reporting an Incident

In the event of any injury or property damage incident, Subcontractor Supervision will contact the Layton Construction Superintendent and obtain an Incident Packet that will contain all of the applicable literature, including:

- Employee Injury Report
- Supervisors Investigation Report
- Witness Statement Form
- Site-Authorization Treatment Form (for CCIP projects)
- Rx First Fill Form (CCIP projects)

These written reports will be submitted to Layton Construction management during the same shift. The subcontractor supervisor will submit a copy of a First Report of Injury form (from a Doctor) to Layton Construction Management the next business day following the doctor or clinic visit. **Failure to comply with these claim procedures will result in a flat fee of \$5,000 to be paid by Subcontractor to Layton Construction for additional costs to manage claim.**

Injury / Incident Flow Chart



INCIDENT INVESTIGATION

All incidents on Layton Construction projects will be thoroughly investigated.

Evidence

It is in the best interest of all parties that all physical evidence not be disturbed or tampered with, regardless of the circumstances involved, unless doing so is necessary for safety reasons, take photographs prior to moving any evidence for documentation purposes if possible. Secure the area of the incident as soon as possible to prevent any alteration of the scene prior to the investigation. If any equipment, tools, or materials were involved in the incident they will be removed from service for safekeeping. If this proves to be impractical the area in which the incident occurred will be cordoned off and security personnel will be posted to keep all unauthorized personnel out of the area. The secure area will only be reopened upon approval from the Layton Construction Safety Manager.

Drawing, Photographs, and Diagrams

Drawings, photographs, and diagrams should be marked up to indicate the location of the accident. All measurements of time, distance, size, weight, etc. must be accurate. In the event of unknowns (e.g. speed, distance, weight), every attempt must be made to closely approximate the same with tables, formulas, or calculations which must be kept as part of the accident investigation.

Incident Investigation Forms

The injured employee will complete the Employee Report Form, which gives personal information so that insurance can be filed on their behalf (in the case of a non-CCIP project the personal information can be omitted from this report). Make sure that the employee fills out the description of incident as completely as possible to assist the investigation team in determining the root cause of the incident.

The injured employee's supervisor will complete the Supervisor Report Form, as well as gather other pertinent documents needed in the investigation (training records, pre-task plan forms, salary data if required, etc.). This supervisor will be expected to keep the Layton Construction project management team apprised of the recovery progress of the injured employee until 100% full release to duty occurs.

Any witnesses in the 30-foot LaPSZ zone should complete a Witness Statement Form, they should consider the "facts" of what they saw the employee doing immediately prior to the incident, including what the witness saw during the morning huddle, pre-task planning, etc.

Preliminary Report

A preliminary report will be completed within 24 hours of an incident. The final investigative report will be completed as soon as possible, but no later than 7 days post-incident. An accurate, detailed narrative description of the operation being performed at the time of the incident is important in determining root cause and corrective actions. Investigative reports should summarize the following: Who was impacted, what happened, when did it happen, and why did it happen. Some things to consider investigating:

- What activities were occurring in the area at the time of the incident (include drawings, photographs, and diagrams)
- What were the weather conditions at the time of the accident?
- Corrective actions required, identify factors that should be considered for correction or additional attention, to prevent a recurrence of the incident. Describe any immediate action taken to correct the circumstances leading up to the incident. List any actions that need further attention
- Recommend if further corrective action should be assigned, and if practical, set a target date for the completion of the corrective action

Root Cause Analysis

A Root Cause Analysis meeting will be held following all significant injury or property damage incidents at the work site to ensure the root causes have been determined and proper corrective action has been initiated. The Root Cause Analysis Form will be completed and filed with the incident report for documentation purposes. The following personnel will attend

this meeting: the injured party, witnesses, subcontractor management (including: supervisor, project manager, and safety representative), and the Layton Management team including Superintendent, Project Manager, and Safety Manager, as well as any others that are deemed appropriate.

The Root Cause Analysis (RCA) involves a closer look at four criteria that may have been a factor in the development of the conditions that led up to an incident.

- Management – Do we have policy enforcement, hazard recognition, accountability, supervisor training, production priority, corrective action, proper resources, craft safety training, hiring practices, maintenance, and adequate staffing
- Employee – Was the employee following procedure, trained, previously injured, mental ability, physical capacity, proper equipment use, utilizing short cuts, and was PPE properly worn
- Equipment – Was the proper equipment used, including tool selection, tool availability, maintenance, tool guarding, visual warnings
- Environment – What about the site layout, chemicals involved, temperature, weather, noise, radiation, terrain, vibration, ergonomics, lighting, biological influences, and ventilation

Post Incident Review Meeting

At this meeting, the Layton Construction project team and Layton Construction senior project management, supervision, and involved subcontractors will follow up on any corrective actions assigned during the Root Cause Analysis Meeting.

RETURN TO WORK POLICY – LIGHT DUTY POLICY

Layton Construction is committed to providing a safe workplace environment for all employees, in the event of a work-related injury Layton Construction has a “Modified Alternate Duty Requirement” which will be implemented by all subcontractors working on Layton Construction projects. The purpose is to minimize the risks and financial burdens to the workforce. Each subcontractor **MUST** provide an injured employee the opportunity to maximize rehabilitation and recovery from the injury and enable an early return to work by accommodating temporary work assignments in compliance with medical restrictions.

Note: Modified duty positions do not have to be on a Layton Construction project. The injured workers’ employer can provide this position at any alternative site. The insurer may provide recommendations for modified duty labor through cooperative organizations if the contractor/subcontractor are unable to accommodate the employee.

The modified duty must include, but not be limited to:

- Communication between the employer and the injured employee and the physician, the employer’s modified duty requirement and facilitate modified duty with physicians and the employee
- The injured employee must provide copies of all medical notes, that include a statement on work capacity.
- Modified duty assignments must comply with all medical limitations as outlined by a physician
- The injured employee is not to assume normal work activities unless there is medical documentation releasing the employee to his/her normal duties

Subcontractor and its sub-tiers must provide a modified return to work program for any of its injured employees insured under workers’ compensation as part of the CCIP. Failure to provide reasonable accommodations to an injured worker will result in a penalty assessment to the Subcontractor of any tier of \$1,500 weekly until such time as the injured worker is returned to work. Subcontractors are responsible for the assessments of their sub-subcontractors.

SUBSTANCE ABUSE POLICY

Layton Construction is committed to providing a safe, drug-free workplace for all employees. This substance abuse policy applies to all Layton Construction, subcontractors of any tier, vendors, and any third-party employees (including management) working on or visiting the project. To ensure safe and productive working conditions and consistent with business necessity, Layton Construction prohibits the use, possession, or distribution on its premises, any of the following: alcoholic beverages, intoxicants, narcotics, illegal or unauthorized drugs or drug paraphernalia. Employees will not report for work under the influence of any illegal or unauthorized drug, alcoholic beverage, intoxicant, narcotic, or other controlled substance. This includes legally prescribed drugs and medicines, which may in any way adversely affect employee’s working ability alertness and/or coordination, or which may adversely affect the safety of others on the job.

Prescription Drugs

Legally prescribed drugs may be permitted on company premises or work locations provided these drugs are in the original prescription container and prescribed for the current use of the person possessing the drug. It is the responsibility of each employee who is taking prescription medication to inform the physician of current job responsibilities, as well as to inform the direct supervisor of any medication that would restrict him from performing duties in a safe and efficient manner.

Drug Testing

Consistent with the intent of this policy, Layton Construction reserves the right to require drug testing of anyone as a condition of employment and thereafter may require randomly selected workers to take drug tests to ensure continuing compliance with the Layton Construction drug policy. Layton Construction also reserves the right to drug test based on reasonable suspicion. Our drug testing facilities specifically test for the following substances: marijuana, cocaine, opiates, barbiturates, amphetamines, benzodiazepines, phencyclidine, methadone, propoxyphene, and alcohol (if post-accident or reasonable suspicion). Additionally, any worker on the project involved in an incident resulting in an injury/illness or property damage are immediately subject to a mandatory drug test. The employee will be sent to a certified drug testing facility, if the sample is non-negative the drug testing facility will send the sample for further analysis. All information, interviews, reports, statements, memorandums, or test results received by Layton Construction will be kept as confidential as possible. Employees may request a written copy of the drug test results and may explain a positive test result in a confidential setting by contacting Human Resources. Employees and prospective employees may request a retest of the original sample at their own expense by contacting the drug testing facility.

Disciplinary Action for Drug Policy Violations

Any employee who violates this policy, including failing to pass a drug test, refusing to submit to a drug test, or tampering with or adulterating a sample will be subject to disciplinary action, including refusal to hire, immediate termination, immediate removal from a jobsite, and future prohibition from the premises. Former employees terminated for violation of this drug and alcohol policy may be considered for rehire with Layton Construction after six (6) months. Additionally, the former employee must successfully complete a drug/alcohol rehabilitation program and must successfully pass a drug test. Alternatively, a former employee may be eligible for rehire if a substance abuse professional determines the former employee is not a candidate for a rehabilitation program and he passes a pre-employment drug test. The former employee must make a personal commitment to remain drug free and to abide by this policy. If rehired, such employees may be subject to periodic unannounced drug testing up to six (6) times within a 12-month period. After a second non-negative drug test, and employee will be terminated and not be eligible for re-hire.

Searches

Layton Construction reserves the right to search any company property, facilities, equipment, employee vehicles, or other personal property located on company property or work sites. Layton Construction may seize any controlled substances and report the same to law enforcement personnel. Refusal to submit to a search may result in suspension and possible termination.

TOBACCO POLICY

Layton Construction encourages a smoke-free workplace. There will be **NO** smoking, e-cigarettes, or chewing tobacco except in designated areas on all Layton Construction projects.

CELL PHONE USE POLICY ON LAYTON CONSTRUCTION PROJECTS

Cell phone and phone camera use on Layton Projects will be limited to emergency, company or project-related business (BIM360 Field checklists). Serious accidents are on the rise due to individuals talking, texting, or using apps while walking. No radios, iPods, earbuds, etc. are allowed on any Layton Construction project site. Personal devices are only allowed during company approved breaks. If emergency use is anticipated, notify your supervisor of the expected need to receive personal communication. Individuals using cell phone or mobile devices (iPads or IOS devices for BIM360 Field) **MUST** position themselves out of the line of fire and remain stationary while completing the task. Once the task has been completed, the individual will look around prior to walking again.

ABSOLUTELY NO CELL PHONE USE WHILE OPERATING EQUIPMENT, OR VEHICLES WHILE ON THE PROJECT!

PERSONAL PROTECTIVE EQUIPMENT (PPE)

OSHA 29 CFR 1926.28 requires that a PPE assessment be completed prior to commencement of any work activity. All Layton Construction employees, subcontractors, vendors, and third-party individuals will at a minimum wear the following personal protective equipment (PPE without exception while on the project (except in the office, lunch areas, and enclosed cabs). Additional PPE may be required based upon the PPE assessment.

Head Protection

Hardhats must meet ANSI Z89.1 standard and will be worn in accordance with manufacturer's recommendations. Hard hats will be worn at all times on the project. Employee's name must be displayed on the front of the hard hat so that a person speaking to them can easily see this information.

Eye and Face Protection

Eye and face protection safety glasses that meet ANSI Z87 criteria will be worn at all times. Employees with prescription glasses must meet ANSI Z87 requirements or they will be required to wear over the glasses (OTG) safety eyewear. Clear safety glasses are required as a minimum in all interior work situations and low light conditions. The following eye/face protective equipment must be used when performing the following work activities:

Activity	Safety Equipment
Welding	Welding hood and safety glasses with side shields
Burning	Burning goggles with shield
Abrasive Grinding or Cutting	Face shield and safety glasses with side shields
Drilling	Goggles or face shield and safety glasses with side shields
Reaming	Face shield and safety glasses with side shields
Chemical Handling	Goggles and face shield
Molten Materials	Goggles and face shield
Corrosive Liquids	Goggles and face shield
Concrete Pouring	Safety glasses with side shields

Foot Protection

Sturdy, above the ankle work boots that are in good condition must be worn (heel and sole will not show excessive wear). Tennis shoes, sandals, or other street-type shoes are not allowed, even if they have steel toes. Some clients may require steel-toed boots, employees will be required to have these boots if it is a requirement on the project.

High Visibility Attire

Every worker, visitor, and vendor will wear high-visibility attire at all times. ANSI reflectivity requirements must be complied with when working in traffic and/or at night. Only welders are excluded from this requirement while performing welding operations.

Work Attire

Shirts will have a minimum sleeve length of three (3) inches. Tank tops, and cut-off shirts are not permitted. Long trousers that fit properly around the waist and ankles and are proper length as to not present a tripping hazard. Trousers that are worn low on the hips or high are not allowed. Shorts are not permitted.

Respiratory Protection

A Competent Person will determine if a hazard exists which requires respiratory protection prior to start of work. Written documentation supporting this hazard assessment will be made available to Layton Construction upon request. Whenever respirator protection is deemed required or requested by a worker on the project, the requirements outlined in OSHA 29 CFR 1926.103 will be followed, including completing a medical questionnaire for respirator use, which will be reviewed by a physician or licensed health care professional. The appropriate type of respirator will be selected to protect employee from the hazard, including any training needed or required. All employees wearing respirators will be fit-tested.

Hand Protection

Hand and finger protection will be specifically addressed in the development of the Daily Pre-Task Plan and the appropriate protection will be identified. Each employer's Competent Person will assist in recommending the correct glove for the task. While handling tools or materials craft workers will wear gloves at all times to prevent hand and finger injuries.

Hearing Protection

Approved hearing protection will be worn as specified in posted areas and while working with or around high-noise level (about 85dBA) producing machines, tools, or equipment. A good rule to follow is if you must raise your voice to be heard, you need hearing protection. Exposure to impulsive or impact noise will not exceed 140dB noise level.

Duration per day (hours)	Sound Level dBA Slow Response
8	90
6	92
4	95
3	97
2	100
1 ½	102
1	105
½	110
¼ or less	115

Impulsive or Impact Noise

Equipment or Tools	Sound Level Created
Pneumatic chip hammer	103-113
Jack hammer	102-111
Concrete joint cutter	99-102
Chop saw	88-102
Stud welder	101
Bulldozer	93-95
Crane	90-96
Hammer	87-95
Backhoe	84-93

Additional Protections

Where engineering and administrative controls do not fully mitigate the hazard, Layton Construction may require workers to wear additional personal protective equipment (PPE) to reduce the likelihood of a work-related injury or illness.

SANITATION

Toilet Facilities

Adequate chemical toilets are available on the jobsite for the use of employees. Chemical toilets will be serviced often enough to prevent overflowing, creation of unsanitary conditions, a health hazard or nuisance, and will be maintained and in good repair to prevent leakage of the contents to the surrounding areas. The facilities will be placed to ensure easy access/egress.

Wash Facilities

Wash facilities will be available at the jobsite for washing hands prior to eating or drinking.

Drinking Water

Employers will provide daily, fresh clean drinking water to their employees. Drinking water will be dispensed in containers with a tight sealing lid and labeled as Drinking Water. Drinking water containers are to be cleaned daily. Adequate cups will be made available at each drinking water container. Cups will be stored in a durable clean dispenser. A trash can or other receptacle will be provided to collect used cups. Contractors are responsible for cleaning up around the water container area daily. The dipping of cups into the container, storing soda cans and bottles, drinking directly from the spout, or placing hands or other material into the drinking water is prohibited. Employers have the option of providing plastic disposable water bottles instead, unless prohibited in the contract. If water bottles are provided, they need to be disposed of properly.

HEAT ILLNESS PREVENTION

To control the risk of heat-related injury or illness on Layton Construction projects the following heat illness prevention program will be followed by all subcontractors and sub-tiers on any Layton Construction jobsite. Projects in California will reference CAL OSHA Title 8 3395.

Provision of Water

Water is a key preventative measure to minimize the risk of heat-related illness. All employees will have access to potable drinking water in sufficient quantity for the entire work shift. All subcontractors will have sufficient water supplies in all

locations where craftsmen are working (see Drinking Water section). The frequent drinking of water will be encouraged by supervisors.

Access to Shade

Access to rest and shade or other cooling measures are important preventative steps to minimize the risk of heat related illnesses. Employees will be provided access to an area with shade that is either open to the air or provided with ventilation or cooling for a period of no less than five minutes if they feel that they need a recovery period from the heat. Such access to shade will be permitted at all times. Employees will have access to an office, construction trailer, or other building with air conditioning. Employers will provide an area for employees to take breaks which are readily accessible, in the shade and open to the air or ventilated and cooled, and near sufficient supplies of drinking water.

Written Procedures

Written procedures help reduce the risk of heat related illnesses and ensure that emergency assistance is provided without delay. The written procedure will be used during applicable trainings such as weekly safety meetings, tool box talks, or other training forums as needed. The written procedure will include recognition of symptoms of heat illness, and how to respond if medical intervention becomes necessary. This will include how Emergency Medical Services will be provided should they be necessary. When a heat illness is suspected, the injured person will be taken to a cool shaded area and evaluated, proper medical treatment will be administered until Emergency Response arrives.

Training

Training is critical to help reduce the risk of heat-related illnesses and to assist with obtaining emergency assistance without delay. All employees including supervisors will receive training on the following:

Employer's written program and procedures related to heat illness prevention and treatments, including procedure for contacting emergency medical services if required.

Immediate reporting of any symptoms or signs of heat illness

Environmental and personal risk factors, including the common signs and symptoms of heat illness

The importance of frequent consumption of water, up to 4 cups per hour, when working in hot environments

All supervisors will receive periodic additional training in heat related illness prevention methods

DAILY HUDDLE AND STRETCH AND FLEX

Prior to the commencement of work, a huddle will be held where all subcontractors and their employees that will be working during that shift will be assembled. This time serves for general announcements, events unique to that day, and recognition of good work completed on the project. Research suggests that most re-occurring and disabling injuries that plague the construction industry are soft tissue injuries, to mitigate this trend warm-up and stretching will be included in the Daily Huddle.

MAXIMUM LIFTING POLICY

Layton Construction Company has implemented a 75 lbs. maximum lifting requirement for all employees and craft workers on any Layton Construction project. Proper training and lifting mechanics will help ensure that 75 lbs. can be lifted without injury, but generally the 50-75 lbs. range should be avoided as much as possible. In general materials weighing greater than 75 lbs. should be moved by carts, dollies, pallet jacks, forklifts, or crane/hoists. There may be special circumstances when individuals may have to manually move material weighing over 75 lbs. Anytime material greater than 75 lbs. is to be moved manually, hazards associated with the same should be discussed during the Daily Pre-Task Planning by each crew.

UTILITY PROTECTION POLICY

Prior to start of work that could possibly interrupt any live utility, the Layton Construction Superintendent and the subcontractor creating the exposure must complete the Layton Construction Utility Protection Permit. Work could include: excavation, demolition of any scale, concrete cutting, core drilling, and re-work or floor/wall/roof penetrations. The permit process is meant to force critical pre-planning and to establish the means to discover, identify and mark the locations of utilities, and to ensure all affected crafts in the area are aware and educated on the protection system. Superintendents will include utility protection as a topic in the weekly subcontractor coordination meeting.

Layton Construction Superintendent and subcontractor will identify the work activity that could cause a utility interruption. The subcontractor will be provided the Utility Protection Permit checklist in BIM360 Field (see Appendix 17) and will complete all sections with assistance from Layton Construction Superintendent if needed. Discovery methods used to locate utilities will be scheduled and completed with findings reviewed and posted if necessary. Following discovery all employees or affected crews in the area will be trained on live utilities or protected methods in place. This information will be documented in BIM360 Field to include any training(s) and requisite signatures.

ENVIRONMENTAL POLICY

Layton Construction is committed to protecting the environment by identifying and complying with all local, state, federal, and client regulations and requirements. It is the responsibility of Layton Construction, subcontractors, vendors, or other third-party individuals to help identify and analyze Environmental Safety and Health (ESH) regulations and work with the Layton Construction ESH Managers to coordinate any concerns. Outside legal representation may assist with regulatory interpretations as needed. It will be the responsibility of all subcontractors to comply with the regulations. Prior to commencement of construction activities, a comprehensive search that identifies relevant federal, state, and local regulations will be conducted. Any regulation that apply to the operation will be identified and a specific plan of compliance will be developed.

Non-Hazardous Materials

All non-hazardous materials and trash will be put in the contractor provided trash containers. Housekeeping will be done daily without exception.

Hazardous Materials

In the event of a spill of one quart or more of petroleum type and/or other hazardous substance, the Layton Construction ESH Manager will coordinate containment with the subcontractor. Once the spill is contained, Layton Construction will coordinate clean up and disposal with the owner. All work will actively stop in the immediate area of the hazardous material spill and will not resume until the area has been cleaned and released by the Layton Construction ESH Manager. A 20-pound ABC Fire Extinguisher will be placed near the spill area, no closer than 25 feet and no further than 50 feet and will remain until remedial activities are complete

Water

In order to prevent the contamination of water, the Storm Water Pollution Prevention Plan (SWPPP) will be developed by a Qualified Person. Before site work commences, best management practices will be installed in accordance with the SWPPP plan.

AIR POLLUTION CONTROL PLAN

The written Air Pollution Control Plan is to establish requirements to prevent or minimize air pollution associated with on-site construction activities. The requirements should comply with all federal, state, and local laws, regulations, and standards. Where local or state regulations require more stringent or different controls, the project must incorporate those requirements into the Air Pollution Control Plan. The Air Pollution Control Plan (APCP) applies to all subcontractors and their sub-tiers.

Site Preparation and Vehicular Traffic

Many local jurisdictions require that a dust control plan be prepared and submitted for approval prior to beginning site preparation or earthwork. Prior to beginning construction, a dust control plan should be obtained from the earthwork subcontractor. The dust control plan must be included in the site specific APCP. The dust control plan must include the criteria and frequency for applying water to potentially dusty areas of the site subject to vehicular traffic.

Demolition

The demolition of buildings, tanks, and piping systems can often result in the release of air pollutants. Depending on the age of the building, these materials could contain asbestos, or lead-based paint. Ductwork or pipes may contain residual chemicals of concern such as arsenic, adhesives/coatings, solvent, or petroleum vapors. Tanks may contain materials that can release vapors or pose a potential hazardous situation when being removed. State and/or local permits are usually required for demolition of asbestos-containing/coated structures, pipes, and equipment or for removal of underground

fuel/chemical tanks. A certified asbestos removal contractor will be used for any asbestos removal activity. All permits and licenses must be available for review. Sand/bead blasting of metal tanks, heavy equipment and steel structures generates spent abrasive material and residual rust and paint chips. The paint being removed may contain lead, requiring additional steps to be taken to prevent the release of these materials. Prior to removal, dismantling, or disassembly of tanks, pipes, pumps, or valves, they must be checked to verify that they contain no liquids, sludge, or residues. These residues must be removed in accordance with government, owner, and contractor requirements prior to demolition.

HAZARD COMMUNICATION

All workers on the project are entitled to know the properties and potential safety and health hazards of chemicals or substances that they may come in contact with on the project. Each project will develop a written project specific Hazard Communication Plan. This plan will be placed in a location where workers can easily access and review the plan and the SDS. Prime subcontractors will submit to Layton Construction a copy of the Safety Data Sheets (SDS) of all known hazardous chemicals that are in their work area including all sub-tier subcontractors.

It will be the responsibility of each prime subcontractor supervision or Project Manager to ensure SDS are received prior to the time of delivery of a hazardous chemical. Prime subcontractors will keep SDS on location for each hazardous chemical or substance used on site. Project management and front-line supervision will ensure all hazardous chemicals are properly labeled in accordance with the SDS. Containers that hazardous chemicals have been transferred into for use during a single shift will be properly labeled.

Each worker will receive training on the Hazard Communication Program, the location of the location of the SDS, labeling requirements, and any specific safety or health instruction about the hazardous chemical or substance. Prior to exposure or use of any hazardous chemical or substance workers will be trained in physical and health hazards, required PPE, procedures to protect against the hazards, emergency procedures in case of exposure or accidental spill, engineering and administrative controls, and labeling requirements. Whenever a new chemical or substance is introduced into the workplace, workers will be briefed of its hazards during Pre-Task Planning.

Anyone that may have business in or near a work area that hazardous chemicals are being used will be notified of the hazards they may encounter. If a worker believes they have encountered a hazardous chemical or substance unfamiliar to them, they will immediately notify a supervisor. Project supervision will attempt to identify the hazardous chemical or substance and initiate all precautions to handle and dispose of the material.

LAYTON CONSTRUCTION SITE SPECIFIC STANDARDS

The standards below have been selected for this project following an analysis of risks and processes anticipated for the anticipated scope of work. It is important to note that in the event a standard or policy is not included the relevant standards in CFR 1910 and CFR 1926 the OSHA standards remain in effect.

ASBESTOS PROCEDURES/PROCESSES

Asbestos containing material (ACM) and/or presumed Asbestos Containing Material (PACM - certain materials pre-1980) are classified as hazardous material by OSHA and the EPA. It is never the intent of Layton Construction to include asbestos removal/abatement in the scope of work. All hazardous material abatement will be the responsibility of the building owner. Any scope of work requiring demolition (no matter quantities) will require a complete asbestos inspection/survey by the building and/or facility owner to determine the presence, location, and quantity of ACM and/or PACM.

In the event that ACM is discovered or disturbed, Layton Construction ESH VP, CEO, and in-house Council must be notified immediately. A contracted asbestos expert will be contacted to advise and ensure proper notification, protection, best practices, and protocol are followed, and the owner will begin the abatement process. Only a licensed contractor will repair and/or abate disturbed or damaged ACM/PACM material. When ACM/PACM is found, all work will stop and possible exposed crafts will be removed from the area. All notifications will be made, proper labeling and material control measures will be put in place until the hazardous material is abated. The immediate area at the ACM/PACM will be barricaded with no entry until authorized by Layton Construction.

All Layton Construction employees will complete annual asbestos awareness training to provide a general understanding of the hazards and responsibilities when ACM/PACM is introduced into the scope of work, including known ACM products, cancer and lung effects, and protective measures. All subcontractors will provide proof of employee asbestos awareness training for those employees working onsite that may come into contact with areas that contain ACM/PACM.

Pre-Construction

Identify and consult the certified asbestos inspector/expert that will help evaluate facility asbestos inspection completeness relevant to Layton Construction scope of work and provide support if ACM is discovered after abatement. The asbestos inspection report is to remain at the project, through completion, for review by employees or regulators, if requested. Work will not start on any project requiring demolition until the asbestos inspection is provided by the facility owner (per OSHA regulations 1926.1101(k)(2)(i)). The asbestos report, locations and quantities of ACM/PACM will be communicated to the subcontractors that will be exposed to these sites prior to work beginning. This notification will be documented in a pre-construction orientation. ACM material that will remain in the facility during the renovation will be posted/identified and all crafts with possible exposure will be notified of the ACM location and the requirement not to disturb.

LEAD

It is never the intent of Layton Construction to include quantity of lead removal/abatement in the scope of work. All hazardous material abatement will be the responsibility of the building owner. Any scope of work requiring demolition (no matter quantities) will require a complete asbestos inspection/survey by the building and/or facility owner to determine the presence, location, and quantity of lead.

SILICA

In an effort to limit worker exposure to respirable silica employers must plan tasks and training to meet OSHA standards CFR1926.1153(k) Respirable Silica and CFR 1910.1200 Hazard Communication Standard. Exposure tasks may include: using masonry saws, grinders, drills, jackhammers, handheld powered chipping tools, operating vehicle-mounted drilling rigs, milling, operating crushing machines, and using heavy equipment for demolition tasks. Employers following the requirements outlined in Table 1 (See Appendix 16), it will be assumed the work falls below the permissible exposure limit. Table 1 lists 18 silica-generating tasks along with specific engineering controls and respirator requirements. The employer is responsible to ensure exposure limits are not exceeded. Employers who DO NOT follow the requirements outlined in Table 1 will be required to measure workers' exposure to silica and independently decide which dust controls work best to limit exposures to the permissible exposure limits in the workplace. Regardless of which exposure control method is used, all construction employers covered by the standard are required to:

1. Establish and implement a written exposure control plan that identifies tasks that involve exposure and methods used to protect workers, including procedures to restrict access to work areas where high exposures may occur.
2. Designate a Competent Person to implement the written exposure control plan and train workers on work operations that result in silica exposure and ways to limit the exposure.
3. Restrict housekeeping practices that expose workers to silica where feasible alternatives are available.
4. Offer medical exams, including chest X-rays and lung function tests, every three years for workers who are required by the standard to wear a respirator for 30 or more days per year and keep records of workers' silica exposure and medical exams.

CONCRETE CONSTRUCTION

All vertical and horizontal rebar, form stakes, metal and/or plastic conduit, and/or small pipe stub-ups will be protected with approved caps or other industry accepted alternatives to protect against impalement and injury. Workers that will operate vibrators, pump nozzles, and concrete buckets will wear appropriate eye and foot protection. Long sleeve shirts will be worn to protect bare skin from exposure to concrete and the possibility of concrete burn and contact dermatitis. Finishers will wear kneepads and impervious gloves when hand-finishes concrete.

Workers engaged in vertical rebar assembly will comply with the six-foot fall protection rule. Positioning devices alone are **not** approved fall protection but can be used in conjunction with personal fall protection equipment. Walkways along form walls will be constructed in accordance with OSHA scaffold and fall protection standards.

Pre-fabricated forms and form making material will be stacked neatly at all times. When stripping concrete forms, all material will be immediately removed and stacked in an orderly manner. Forming material or debris will not block walkways and aisles. Subcontractor will remove rebar, tie-wire and other debris from the work area daily. Ensure that reinforcing steel and forms for walls, piers, columns, stairs, and similar vertical structures are adequately supported to prevent overturning or collapse and are designed and installed under the supervision of a Qualified Person. Ensure that uncoiled wire mesh is adequately secured to prevent recoiling.

Equip buckets with a discharge device that an employee can operate without being exposed to the load. Equip buckets with safety devices to prevent premature or accidental dumping and ensure that the release is self-closing. Follow safe rigging practices when handling concrete buckets. No employee is permitted to ride a concrete bucket. When using bull floats, inspect the area to insure there is no energized equipment or power lines nearby that the handles could touch. Concrete buggy handles must not extend beyond the wheels on either side of the buggy. Rotating-type powered concrete trowels will be equipped with dead-man controls that automatically shut down the equipment when the operator's hands are removed from the controls.

Post-tensioning Operations

No worker(s), except those essential to the post-tensioning operation, will be permitted behind the jack. Warning signs and barriers will be erected to limit access to the post-tensioning area during post-tensioning operations.

PRECAST CONCRETE

A Qualified Person is required to be responsible for the inspection of all rigging and hardware and the supervision of the rigging of precast concrete members.

Unloading of Precast Concrete Members

Prior to precast concrete members being unloaded, all rigging and hardware will be inspected, the precast member is properly rigged, and the load is stable before releasing the binders.

Placement of Precast Concrete Members

Precast members are not to be moved over workers. Workers involved in the setting or connecting of precast members will strictly adhere to the 100% fall protection policy with no exception. No worker will use hands to reach under a precast member to adjust a shim or bearing pad.

CONFINED SPACE

Layton Construction is classified as the Controlling Contractor per OSHA 29 CFR 1926 Subpart AA Construction confined space and will be the primary point of contact for information about permit spaces at the work site. The Host Employer (Owner) must provide information it has about permit spaces at the work site to the Controlling Contractor, who then passes it on to the subcontractors whose employees will enter the spaces.

Prior to commencement of work, each employer must ensure that a Competent Person has identified all confined spaces in which any employee may work and identifies each space that is a permit space, through consideration and evaluation of the elements of that space, including testing as necessary. All Entry Employers conducting work on a Layton Construction site will decide how employees it directs will enter a permit space, the Entry Employer must have a written permit space program implemented on-site. Entry Employers must give Layton Construction information about the entry program and any hazards they encounter in the space. Prior to any worker entering a confined space, they will submit training records to Layton Construction, this training will include: Contents of the Confined Space Entry Plan, known hazards in the confined space, emergency procedures in case of an emergency, correct use of PPE (when required), Hot Work Permit (if required), atmosphere testing requirements, Lockout/Tagout procedures, and fall protection (if required).

Entry certification and confined space entry permits must comply with 29 CFR 1910.146 and 29 CFR 1926 Subpart AA, Confined Spaces in Construction. There are 5 key differences in the construction rule, and several areas where OSHA has clarified existing requirements. These new standards address more directly the needs of the construction industry.

- More detailed provisions requiring coordinated activities when there are multiple employers at the worksite. This will ensure hazards are not introduced into a confined space by workers performing tasks outside the space. An example would be a generator running near the entrance of a confined space causing a buildup of carbon monoxide within the space
- Requiring a Competent Person to evaluate the work site and identify confined spaces, including permit spaces
- Requiring continuous atmospheric monitoring whenever possible
- Requiring continuous monitoring of engulfment hazards. For example, when workers are performing work in a storm sewer, a storm upstream from the workers could cause flash flooding. An electric sensor or observer posted upstream from the work site could alert workers in the space at the first sign of the hazard, giving the workers time to evacuate the space safely
- Allowing for the suspension of a permit, instead of cancellation, in the event of changes for the entry conditions listed on the permit or an unexpected event requiring evacuation of the space. The space must be returned to the entry conditions listed on the permit before re-entry

Procedures to ensure safe work on Layton Construction work sites for all personnel who enter confined spaces will cover: the requirements for safe entry, work, and exit of personnel assigned to work in confined spaces. These requirements apply to all Layton Construction staff and include subcontractors and sub-tiers. Identification of confined spaces (aka equipment, tanks, vessels, silos, storage bins, hoppers, vaults, pits, manholes) which have the following physical characteristics:

- Large enough and so configured that personnel can bodily enter and perform assigned work (this includes spaces where the head and trunk can enter even if the whole body could not fit)
- Limited or restricted means for entry or exit (aka man-way door, hatch, cover)
- Not designed for continuous personnel occupancy (aka a hazardous situation is typically present in the space)

If all three conditions above are present, the space is a confined space. Proceed to classify the confined space based on the potential hazard in the space.

MOBILE ELEVATED WORK PLATFORMS (MEWPS)

The overhead and underground utility considerations for aerial lifts are located in the crane section of this document.

Scissor lifts will be used in accordance with 1926.452(w). Aerial lifts will not be used as material hoists unless the load is contained within the basket and meets the lift's rated capacity. The lift will not be modified for hoisting material unless the manufacturer approves in writing. The gates of aerial lifts will be properly engaged whenever the lift is in use.

Suspended Scaffolds

A Competent Person will evaluate suspended scaffolding and anchorages and suspension lines before each use. Workers working from suspended scaffolding will wear a full body harness attached to an independent vertical lifeline. When welding is required from swing stage scaffolding, the scaffold will be grounded and suspension ropes protected. In all cases activities will be consistent with manufacturer's recommendations.

Mobile Scaffolds (aka Baker Scaffold)

It is recommended that handrails be in place anytime the working platform is in excess of 4 feet above the ground, but is MANDATORY that handrails be in place at six (6) feet above the ground. Wheels on mobile scaffolding will be locked in place when workers are working from it, self-propelling is prohibited.

CRANE SAFETY

Every crane operating on a Layton Construction project must have the following documentation in the cab of the crane available for review: Manufacturer's operating manual, manufacturer's lift charts, last annual inspection, last monthly inspection, and exception reports (if any).

Operator, Rigger, and Signalman Qualifications

All crane operators on Layton Construction projects are to be a certified crane operator (CCO) and possesses all of the requisite skills and demonstrate requisite skills to safely operate the applicable equipment. However, until CCO's are available at all US locations, Layton Construction will make every effort to use operators who are certified by the National Commission for the Certification of Crane Operators (NCCCO) for the cranes they are operating. Prior to any lifts the operator's competency will be verified through their employer and made available to Layton Construction Site management. This certification does not ensure that an operator is capable of safely operating a particular piece of equipment.

Qualifications for riggers and signalmen will be compliant with OSHA standards, verification of certifications must be presented to Layton site leadership prior to crane operations.

Required Certifications

Review and inspect NCCCO Certification Card for type of cranes the operator is certified to operate. Verify on the application for employment or by subcontractor certification that the applicant has operated cranes in the classification for which they are being hired. Layton Construction reserves the right to remove an operator from the site if, in Layton Construction's judgment the operator is unfit to operate the applicable crane. Upon determining that the potential operator is qualified, project specific training will be given to the operator.

Inspection and Oversight Requirements

Ongoing comprehensive inspections are a critical component that ensures the on-going safe operation of all cranes. Prior to any crane arriving on a Layton Construction project, the previous monthly and annual inspection will be submitted and reviewed by Layton Construction site management. Verification that all noted defects have been corrected will be included with the inspection form. A **qualified** third party will inspect all structural components in accordance with manufacturer's recommendations. The crane rental company will perform all maintenance and inspections in accordance to manufacturer recommendations. The erection of tower cranes will be directed by a third-party inspector and upon completion of erection a new annual inspection will be accomplished and all defects corrected and documented prior to any lift.

Daily Inspections must be accomplished by a Qualified Operator and documented in BIM360 Field for all cranes on a Layton Construction project. It is mandatory that the equipment checklist is used to document that this requirement has been met. Monthly Inspections will be accomplished for all cranes used on the project for greater than 21 days or 3 consecutive weeks, regardless of operating days during that period. The monthly inspection forms are required to be completed and maintained in the cab of the equipment, and a copy uploaded into BIM360 Field for project documentation. Monthly forms will be retained for a minimum of three (3) months and some local agencies may require them to be retained longer. Annual Inspections will be accomplished for all cranes used on that project for greater than 365 calendar days, regardless of operating days during that period. The annual inspection must be accomplished by either a vendor, manufacturer, or third-

party inspector and the forms maintained in the cab of the equipment, with a copy uploaded in BIM360 Field for project documentation.

FAA and Other Agency Notifications

The Federal Aviation Administration (FAA) requires a permit on construction cranes any time they will exceed 200 feet in height, **OR** when they are placed within 20,000 feet (3.79 miles) of an airport regardless of height. The FAA required FAA Form 7460-1 to be submitted at least 30 days before the date the proposed construction is to begin, the date the application for a construction permit is to be filed, the FAA requires that four (4) copies of the FAA Form 7460-1 be sent to the local/regional FAA Director. In addition to the FAA, other local statutes may require additional notification.

Pre-Erection Requirements

Geotechnical Requirements: soil conditions must be fully assessed prior to any crane arriving at the site. Items to consider include travel, slope, and soil loading ability. Prior to the erection of any tower crane a geo-technical evaluation will be accomplished and incorporated into the foundation design of the engineered system. For mobile cranes, outrigger size, location, and soil condition must be considered when planning. Soil bearing capacity is to be determined by a vendor and outrigger sizing established prior to the crane arriving onsite. Tower crane foundations must be a designed system, certified by a professional engineer, taking all loads and soil conditions into consideration.

Overhead and Underground Utility Considerations

Prior to the assembly/erection of any crane it must be determined if any part of the crane, load line, or load (including rigging and lifting accessories) could get in the direction or area of assembly within proximity of a power line. Minimum clearance distances are on the table below. In the event this clearance must be encroached the line will be de-energized prior to the planned encroachment. If the voltage is unknown, a 20-foot minimum clearance must be maintained.

Voltages (nominal kV, alternating current)	Minimum clearance distance (feet)
Up to 50	10
Over 50 to 200	15
Over 200 to 350	20
Over 350 to 500	25
Over 500 to 750	35
Over 750 to 1000	45
Over 1000	As established by the power line owner/operator or registered professional engineer who is a Qualified Person with respect to electrical power transmission and distribution

Lift and Pre-Task Planning

Prior to any lifts a lift plan will be completed, reviewed, and signed off on by the Senior Superintendent and Safety Manager. The final lift plan should fully incorporate the current site conditions, including utility locations and any possible intersections with public access areas. A Daily Pre-Task Plan must be accomplished prior to any lift for that particular day to ensure that no deviations from the lift plan exist.

Crane Incidents

All incidents involving crane operations (aka unsafe observation, near miss, etc.) must be reported immediately to Layton Construction Project Management, including the Safety Manager. Layton Construction will collaborate with other subcontractors if appropriate and develop a corrective action plan in response to the cause of the incident prior to resuming any crane operations.

Dismantling Cranes

A written crane plan is required for the dismantling of any crane.

Critical and Major Lift Planning and Procedures

The decision to designate a lift as a critical lift is a management decision, incorporating both critical and major lifts.

Guidelines provided here are intended to aid in making that decision. The manager who has the responsibility for the item being lifted has the authority to require that it be handled as a critical lift. In addition, the manager at the facility where the lift will be performed also has the authority to require that it be handled as a critical lift. The manager who designated the lift as a critical lift will ensure that a person-in-charge (PIC) is assigned. The PIC need not be in the Layton Construction Organization. A definition of a critical or major lift is: if load reaches 75% of the crane's maximum capacity, two (2) or more cranes are needed to make a pick, or when hoisting personnel.

The PIC will ensure that a step-by-step procedure is prepared for all critical lifts. Although individual procedures are prepared for the one-time critical lifts, general procedures may be employed to accomplish routine recurrent critical lifts. Any non-routine or critical equipment lift (as determined by the Project Manager, Superintendent, or Safety Manager).

Critical equipment may include equipment that meets one of the following criteria:

- The load item if damaged or upset would result in a release into the environment of radioactive or hazardous material exceeding the established permissible environmental limits
- The load item is unique and, if damaged, would be irreplaceable or not repairable and is vital to a system, facility or project operation
- The cost to replace or repair the load item, or the delay in operations of having the load damaged, would have a negative impact on the facility, organization, or budget to the extent that it would affect program commitments

A lift not meeting the above criteria will also be designated critical if mishandling or dropping of the load would cause any of the above noted consequences to nearby installations or facilities. Further site-specific criteria may be developed to supplement those cited above and may include loads which require exceptional care in handling because of size, weight, close-tolerance installation or high susceptibility to damage as well as lifts using multiple pieces of lifting equipment.

Approval and Revision of Critical Lifts

The critical lift procedures should be reviewed at a pre-lift meeting by the responsible contractor, the crane operator(s), Layton Construction Site Management, ESH Manager, author of the Lift Plan, and Manager of the lift operation. Any revisions to the procedure will be reviewed and approved through the same cycle as the original procedure.

Pre-Lift Meeting

Before any critical lift is performed, a pre-lift meeting with all participating personnel will be held. During the meeting, the critical lift procedures will be reviewed and questions will be resolved. The pre-lift meeting will be documented. Practice lifts are recommended (if used, requirements for the practice lifts should be documented in the procedure).

Jumping Cranes

Jumping of cranes must follow similar protocols as a critical or a major lift and requires a comprehensive written plan to address the following:

- Number of sections to be added/removed
- Work sequences
- Rigging to be used
- Inspection of all rigging equipment including shackles, hooks, etc.
- Review of all equipment such as collars, ties, and bolts, including capacities and a record of visual inspection by a Competent Person
- Relevant weather warnings and emergency procedures
- Full compliance with manufacturer's recommendations

Accessible areas within the swing radius or the rotating superstructure must be barricaded to prevent serious injury or death to workers. Crane baskets are not permitted without the prior approval of site management and Layton Construction ESH Manager. No employee will work or travel on any part of the crane boom without proper personal fall arrest equipment. No worker will be allowed to climb the tower or get on the boom when the crane is in operation. No load will be swung over any public street that is occupied by the general public unless authorized by local authorities.

RIGGING

Riggers must be properly trained and qualified to rig material or equipment lifted by a crane. Riggers training documentation will be made available to Layton Construction at the pre-mob meeting, if any changes are made in riggers on-site updated training records will be provided prior to any rigging work.

All Hooks will be equipped with safety latches, safety latches on hooks that are disabled and/or shakeout (“pelican”) hooks will not be used unless in compliance with Subpart R 29CFR1926. All rigging equipment and spreader bars will have the manufacturer’s tag. Rigging equipment and spreader bars not tagged or marked will be immediately removed from the project.

All rigging will be inspected daily before each shift, during use, and after use by a Qualified Rigger and documented in writing, and in BIM360 Field Equipment checklist, for Layton Construction documentation purposes. This includes rigging equipment such as chains and slings including nylon straps, continuous chockers and wire rope chockers; as well as all rigging hardware such as hooks and shackles or any hardware used in the rigging of material for lifting and hoisting purposes. In addition, all chain slings such as single chains, or chain 2, 3, and 4 ways or in any configuration will have the following inspected:

- Missing or illegible identification
- Indications of heat damage including weld splatter or arc strikes
- Excessive pitting or corrosion
- Bent, twisted, distorted, stretched, elongated, cracked, or broken load bearing components
- Excessive nicks or gouges
- Evidence of unauthorized (other than the manufacturer) welding or modification
- Swivels unable to freely rotate
- Other conditions including visible damage that causes doubt as to continued use

All chain slings will be returned to the vendor/manufacturer at least annually and have a complete inspection by a Qualified Person to ensure that the integrity of that chain or chain sling configuration is suitable for use (ASME: B30.26- 4.8.4) up to and including the loss of metal not to exceed 10% of the original catalog dimension (ASME: B30.26-4.8.5) all other rigging equipment will meet or exceed the OSHA standard 1926.251, 1910.184 as well as ASME: B30.26-2015).

DEMOLITION

Prior to start of any demolition work, the subcontractor must ensure a Competent Person has performed an engineering survey of the building or area to be demolished to determine the condition and location of utilities, whether hazardous materials exist, means and methods of performing the work, and sequencing. No work will commence until a written engineering survey has been completed and submitted to Layton Construction.

Debris and material will not be dropped through walls, floor holes, windows, or other elevated work areas without the area below being barricaded and properly signed. Under no circumstances will materials be dropped more than 20 feet without using a chute. Debris chutes will have a substantial gate at all elevated openings.

If demolition of a building will involve implosions, the demolition contractor will submit to Layton Construction a detailed safety plan to specifically address site preparation, installation of explosives, debris/dust control and blaster qualifications.

ELECTRICAL

No work will be performed on any energized electrical circuit, bus bars, equipment, or panels unless an approved written work plan is developed in accordance with Chapter 1 of NFPA 70E and submitted to the Layton Construction Superintendent for review prior to performance of work (see Appendix 5 Energized Work Permit). As the General Contractor, Layton Construction is obligated to ensure all electrical subcontractors follow the NFPA 70E standards regulating electrical safety. Temporary lighting will be placed such that adequate lighting is provided at all times during active construction.

Inspection Program

A Competent Person will inspect all cord sets, portable electrical equipment, tools and appliances not part of any permanent building or structural electrical system to prevent any worker from receiving an accidental electric shock. All temporary cords will be three wire types S, ST, SO, or STO with a 16 or heavier wire gauge.

Daily Inspections: Each cord set, attachment cap, plug, and receptacle of cord sets, portable electrical equipment, tools, or appliances connected by a cord and plug, will be visually inspected daily by the user for external damage, such as deformed or missing ground pins, insulation damage, frayed wires or indications of possible internal damage. Any electrical equipment, tool, appliance or cord set that is damaged or defective will be immediately removed from service and tagged out as defective equipment for repair. A Qualified Electrician will repair tagged electrical items.

Monthly Inspections: Each cord set, receptacle, and cord-plug connected electrical equipment, tools, or appliances not part of the building or structure's permanent wiring, will be visually inspected for damage or missing ground pin, insulation damage, frayed or exposed wires, and signs of internal damage. The color of the month tape will be applied following this inspection procedure. Any defective electrical equipment will be immediately removed from service and tagged as defective equipment for repair.

Ground Fault Circuit Interrupters (GFCI)

All cord sets and cord-plug electrical equipment, tools or appliances that are 120 volts will be connected to a ground fault circuit interrupter (GFCI). No cord set or cord-plug electrical equipment, tool, or appliance will be plugged directly into any permanent building or structural electrical system not equipped with a GFCI. When the source of electricity is from a generator, the generator is to be grounded (if required) and a GFCI is required. Each craft worker will periodically inspect, test and reset the GFCI device being used to ensure it is working properly. If the GFCI device is not functioning properly it will be reported to subcontractor supervisor to correct, and if needed to notify the Layton Construction project team.

Double-Insulated Tools

Double-insulated tools are allowable if the case bears the Underwriter Laboratories "double-insulated" label. Tools where this label has been removed, painted over or otherwise not readable must be removed from service.

General Electrical Rules

All cord sets will be elevated above the work surface when practical. Wire, nails, or other conductive material will not be used to hang or attach cord sets or welding leads. Cord sets that cross roadways will be protected from damage from vehicle and equipment traffic by devices such as hose bridges. Light stringers, and halogen lamps will have the light bulbs protected from accidental contact or breakage and will be hung per manufacturer specifications and must have UL listed and be OSHA approved. UL approved covers are required on all panels, load centers, and pull boxes prior to energizing. Necessary steps will be taken to prevent unauthorized or unqualified workers access to energize electrical parts or equipment.

LOCK OUT/ TAG OUT

They Layton project team will establish and Lockout/Tagout procedure to ensure that workers are not exposed to the hazards from moving machinery or equipment and the hazards posed by an energized source (pneumatic, steam, hydraulic, chemical). Refer to Appendix 11 for the Lockout/Tagout Checklist. Safety locks and tags will be applied to all circuits, switches, valves, isolating devices, and any other energy sources to ensure equipment, machinery, or processes, that have been considered functioning, charged, or could otherwise be operable have been rendered non-operational or de-energized.

No person will remove another worker's safety lock or attempt to energize any piece of equipment, machinery or process that has been locked out and tagged.

De-Energizing Equipment and Processes

A Layton Construction representative will coordinate with the operating facility representative when any energized equipment or process must be de-energized. All circuits and sources of energy that require locking and tagging to make the equipment inoperable will be identified. The operating facility representative will notify personnel that may be affected by

the de-energizing. The front-line supervisor for each individual overseeing the work will sign out sufficient safety locks to lockout the piece of equipment, or process.

The operating facility representative and front-line supervisors will make certain the operating controls to the equipment, machinery, or process are in the “off” or “neutral” position. Once verified that the controls are in the “off” or “neutral” position, the operating facility will place a safety lock and tag on the energy isolating device first. Next the front-line supervisor will apply their safety lock and tag to each isolating device that provides power, or other energy to the machinery, equipment or process. The tag will contain the name of the front-line supervisor, company name, date, and phone number. Once the front-line supervisor has placed their safety lock and tag on the energy-isolating device, all affected workers will then apply a safety lock and tag to the energy-isolating device. Alternatively, the front-line supervisor may place the key to the equipment safety locks in a safety lock box, place the individual safety lock and tag on the safety lock box, and then have each affected worker place their safety lock and tag on the lock box.

Prior to any work being performed on the piece of equipment, machinery, or process, the operating facility representative and front-line supervisor will verify that it is inoperable. The operating facility representative will attempt to operate the piece of equipment, machinery, or process. After verifying it is inoperable, the switch will be returned to the “off” or “neutral” position. Stored or residual energy will be dissipated by whatever means are necessary. Capacitors will be discharged and high capacitance elements short-circuited and grounded by a Qualified Electrician.

Re-Energizing Equipment and Processes

When the required work is completed and the machinery, equipment, or process can be returned to service, the front-line supervisor will contact the operating facility representative to notify of completed work operations. The front-line supervisor will make a visual inspection of the equipment, machinery, or process to ensure all workers have completed their work and equipment, tools, and other material is removed from the area.

After confirming all workers, materials, tools, and other equipment are out of the area, the operating controls are still in the “off” or “neutral” position, and each worker has removed their safety lock and tag, the front-line supervisor will remove their safety lock and tag from each of the isolating devices. If a worker fails to remove his or her safety lock at the completion of the job or assigned duties, their immediate supervisor will notify Layton Construction project team and the ESH Manager. Every attempt should be made to contact the worker and require them to return to the project to remove their lock. If the worker is unwilling or cannot return to the project, it must be verified that they are not physically at the project before the safety lock can be removed. All safety lock removal incidents will be investigated following the incident investigation procedure, and disciplinary action will occur.

The management representative will notify the operating facility representative that the equipment, machinery or process is clear to be energized.

De-Energizing Fluid Processes

Layton Construction will coordinate with the operating facility when any fluid process requires de-energizing. Any vessel, pipe, hose, or process that contains a hazardous liquid or gas will be purged with nitrogen or flushed before work begins as described in the Pre-Task Plan for the activity. All valves or gates and where blanks are required to be installed to isolate the work area will be identified.

The front-line supervisor overseeing the work will sign out sufficient safety locks and tags to completely isolate the system. The operating facility representative and front-line supervisor will verify that each valve or gate is in the “off”, “neutral”, or “closed” position. The operating facility representative will place a safety lock on the valve or gate first, then the front-line supervisor will apply a safety lock to each valve or gate and visible warning tag that includes the name of the front-line supervisor, company, date, and phone number. Next all affected workers will then apply a safety lock and tag to the energy-isolating device. Alternatively, the front-line supervisor may place the key to their equipment safety lock in a safety lock box, place their individual safety lock and tag on the safety lock box and then have each affected worker place their safety lock and tag on the lock box. The required blanks will be placed at this time. Prior to commencing work, the operating facility representative and front-line supervisor will verify the system and all piping, hoses, valves, and processes are de-energized, and that any stored energy is dissipated or restrained. Welded valve connections should have the valve

handles removed and the stem tagged “DO NOT OPERATE” all other valves and isolating devices must be physically prohibited from operating. Hydraulic and pneumatic equipment or machinery will be blocked to prevent movement.

Re-Energizing Fluid Processes

The front-line supervisor will make a visual inspection of the area to ensure all workers, equipment, tools, and materials are removed from the area. After confirming this, while the valves and gates are in the “off”, “neutral”, or “closed” position, each worker will remove their safety lock and tag, then the front-line supervisor will remove their safety lock and tag from each of the isolating devices. The management representative will be notifying the operating facility representative that the system is ready to be energized.

EQUIPMENT AND VEHICLES

Only company and/or delivery vehicles used for the sole purpose of conducting work tasks on-site are permitted in construction areas. Equipment used on-site must have an audible backup alarm, and the driver and all passengers of any vehicle will wear seat belts. Rollover protective structures (ROPS) will protect all equipment, including forklifts, and any equipment with a windshield will be free of cracks and other visible damage, seatbelts are required to be worn at all times when provided. Forklifts will have an approved fork attachment for rigging when used to suspend loads from forks, free rigging from forks will not be allowed on any Layton Construction project. Equipment operators will possess the required training, certification, and licenses as required by law for the equipment they are operating. Heavy equipment (cranes, forklifts, dump trucks, excavators/backhoes, man-lifts, etc.) used on the project will be inspected prior to use and comply with applicable OSHA and ANSI standards, which will be documented in a BIM360 Field “Equipment Checklist” daily pre-shift. At minimum the operator will check: brakes, lights, backup alarm and horn, hydraulic systems, steering mechanism, operating controls, mirrors, fire extinguisher, limit switches, and for any leaks.

EXCAVATION AND TRENCHING

Prior to any disruption of ground, excavation, or trenching on the project, Layton Construction will request locations for existing underground private utilities from the owner, and notify public utility locating authorities. All subcontractors will identify the Competent Person and submit qualifications for review and approval by Layton Construction. The Competent Person will analyze the soil of the work area to determine the condition and type of soil to ascertain proper sloping and shoring requirements. The Competent Person will inspect excavations and trenches at the beginning of each day before work begins and when conditions change. Any excavation or trench at four (4) feet or greater in depth will be evaluated for atmospheric hazards. A registered professional engineer must design all excavations over 20-feet in depth.

During excavation or trenching operations on the project, all trenches and excavations will be barricaded and signage posted at the work area. Fall protection will be provided for excavations six (6) feet or more in depth. Trenches or excavations will be sloped or benched in accordance with local rules and regulations, and as determined by the Competent Person (Type C soil will not be benched). Supporting systems (shoring, piling, or trench boxes) will be utilized for all trenches and excavations where sloping or benching cannot be utilized. Spoil piles and all other material will be placed at minimum of two (2) feet from the edges of all activities. When underground utilities are suspected, they will be located first by hand digging, or the use of non-destructive hydro excavation.

Adequate access must be maintained at all times during trenching or excavating activities. Access points will be placed such that no worker travels more than 25 feet in any direction.

FALL PREVENTION/PROTECTION

The project is committed to the philosophy of 100% continuous fall protection whenever workers are exposed to fall hazards of six-feet (6') or greater.

Layton Construction, subcontractors, vendors, or other third-party individuals will take all practical measures to eliminate, prevent, and control fall hazards. When a fall hazard has been identified and cannot be eliminated, then effective means of fall protection will be implemented. Acceptable fall protection systems include:

- Guardrail systems
- Safety netting
- Covers for floor, roof and wall openings
- Protection from falling objects
- Personal fall arrest systems

Workers exposed to fall hazards that cannot be eliminated will be equipped, trained and given periodic refresher training in fall protection to minimize the adverse effects of accidental falls. Fall protection training records will be available for review by Layton Construction. The use of personal fall arrest systems requires the submission of a Rescue Plan for each condition. Elevated work will address protection from falling objects if work below is permitted.

100% FALL PROTECTION MEANS PROTECTION FROM FALL AT ALL TIMES WHEN WORKING AT OR ABOVE SIX-FEET. This means it is mandatory for all trades, including but not limited to:

- Structural steel erection (bolt up and connectors)
- Decking Operations
- Re-bar assembly
- Concrete forming
- Pre-cast erection
- Masonry
- Carpentry
- Scaffold erection/disassembly
- Roofing

Personal Fall Arrest Systems will consist of a full-body harness meeting ANSI requirement, self-retracting decelerating devices (yoyo's) are recommended and shock absorbing lanyards are prohibited. Locking snap hook and anchorage points must meet OSHA regulations, positioning device systems should be used for positioning only they are not a fall arrest system. Workers will not tie off to a perimeter cable or wire rope handrail unless engineered for such use. Subcontractors will submit all engineered documentation on horizontal lifelines to Layton Construction for review and approval. All horizontal lifelines will be installed under the direct supervision of a Qualified Person. Lanyards will not be tied back to themselves unless the lanyard is specifically manufactured to tie back to itself.

When wire rope is used to construct guardrail systems, at least ¼" diameter cable will be used with cable clamps as required by wire rope manufactures. Wire rope will be flagged with high visibility tape or ribbon every six (6) feet. If any component of a guardrail system must be removed, a Layton Construction Guardrail Removal Permit must be issued (Appendix 7). Any contractor that must remove a fall protection system in the course of their work will be responsible for immediately replacing the protective system.

Floor openings 2-inches or greater and all wall opening will be guarded or covered with an appropriate cover or guardrail. Floor covers will be secured to the floor to prevent easy removal. The floor or wall cover will be properly marked with a Danger sign stating "**COVER-DO NOT REMOVE.**"

FIRE PROTECTION PREVENTION

Fire Protection

Layton Construction will develop a Fire Protection Plan in accordance with OSHA 29 CFR 1926 Subpart F. Temporary fire protection measures such as fire extinguishers, temporary hose lines, and temporary standpipes are required during construction. Each temporary building and trailer (shops, field offices, storage boxes, etc.) will have its own appropriately sized and located class ABC fire extinguisher. Access to fire hydrants and extinguishers will be maintained at all times. If a fire extinguisher is discharged for any purpose it will be reported to Layton Construction. Fire extinguishers will be conspicuously located, inspected monthly, and protected from freezing. Fire extinguishers will be placed within the immediate area of any welding/cutting operation or flammable liquid storage area. Fire extinguishers will be placed within five (5) feet whenever gasoline operated equipment is used.

Fire Prevention

Temporary buildings located within another building or structure will be constructed of non-combustible material or have a fire resistance rating of one (1) hour. Plastic tarps or covers (visqueen) used for any purpose inside an occupied building or where welding, cutting, or open flame is present will be made of fire-retardant material.

Combustible refuse from construction operations will not be burned or dumped anywhere on the construction site. Such refuse will be removed at end of shift. Storage of large quantities of construction debris will be placed in metal dumpsters. Oily rags and waste are to be stored separately in metal containers fitted with self-closing lids.

Storage of compressed gasses will include:

- Valves, regulators, and hoses removed with valve caps securely on
- Secured upright at all times, including when transported in vehicles

- Fuel and oxygen cylinders separated by a minimum of 20 feet
- Empty cylinders stored separate from full cylinders; no cylinders in use

Fire and Flammable Liquid Storage and Dispensing

Only approved high flash point solvents are to be used for cleaning purposes, use of low flash point solvents is discouraged. Methylene chloride is a known carcinogen and solvents containing it are prohibited.

Flammable and Combustible Liquids will be stored, dispensed, and used in accordance with OSHA and NFPA Requirements. “**NO SMOKING**” signs will be visibly posted. When stored outside then they cannot be within 20 feet of any structure or they must be in a properly constructed storage locker. Outside storage areas will be kept free of weeds and other combustible materials. Storage of flammables will be in an enclosure away from open flame, heat, direct sun, or other sources of ignition. No more than a total of 25 gallons flammable and combustible liquids can be stored outside of an approved locker. All flammable and combustible liquids will be stored in approved portable containers marked as to contents and ownership.

Fuel and flammable liquid tanks, drums, or barrels will have the proper DOT placard and be labeled as to content. All storage tanks/drums will be placed in a berm or other secondary containment. Berms will be lined with a minimum 6-mil plastic sheeting that is fuel resistant. PVC linings are not allowed. All fuel storage tanks and compressed gas cylinders will be protected from vehicle traffic.

Layton Construction will designate vehicle refueling locations. All fuel dispensing points will be located away from storm drains and wetlands. The following will be required at all refueling locations:

- A portable 20 lb. ABC fire extinguisher will be placed no closer than 25 feet or further than 75 feet from the fueling point
- “**NO SMOKING**” signs will be posted
- Self-locking fuel nozzle prohibited
- Spill kit will be stored nearby
- Tanks will be grounded and when dispensing flammable liquids, the containers will be bonded

HAND AND POWER TOOLS

Hand and power tools are to be operated according to manufactures’ instructions and guidelines and appropriate Personal Protective Equipment (PPE) are to be worn. All hand and power tools will be kept in good condition with regular maintenance.

Fixed Blade Utility Knives

No fixed blade utility knives will be used on any Layton Construction project, only retractable-blade knives will be utilized. Retractable-blade knives feature a handle that is shaped to fit the hand and a push-button slide that fully retracts into the handle for safety and can also be adjusted for cutting depths. Spring loaded retractable blades are preferred.

Hand Tools

- Impact tools such as chisels, wedges, etc. are not to have mushroomed heads
- Wooden handles will not be splintered or cracked

Electric Tools

- Never lift or carry a power tool by its cord
- Guards and safety switches will not be removed or made inoperative
- Electric tools must have a three-wire cord unless it is double insulated

Portable Abrasive Wheel Tools

- Guards will not be removed
- Grinding disks and wheels will be checked to verify they are the correct one for the grinder and rpm

Pneumatic Tools

- Air hoses ½ inch in diameter or greater will have a safety excess valve installed at the source of air
- Clips, whips, or retainers, are required at each air hose coupling and to prevent attachments from being ejected from the tool.
- Only the pneumatic nail guns requiring the muzzle to be pressed against the work surface to fire are allowed.
- Hose couplings will be secured to prevent displacement
- Pneumatic nail guns will be disconnected from the air supply when unattached

Powder Actuated Tools

- Workers will be certified/authorized to operate a powder actuated tool and required to carry their training card at all times
- Fired cartridges will be placed in a container or bucket and properly disposed
- The powder-actuated tool must not be able to fire until it is placed against the surface with a force of 5 pounds or greater
- Misfired cartridges are to be placed in water for 48 hours

HOT WORK OPERATIONS

Hot work activities include burning, welding, cutting, grinding, or other operations that produce a flame or sparks. Prior to performing “Hot Work” operations, workers will complete a Hot Work Permit in BIM360 Field (Appendix 9) from Layton Construction.

General Requirements

A Hot Work Permit will be issued before any hot work is performed. Any welding, flame cutting, brazing, grinding, any work that produces sparks, as well as use of portable heaters, fuel, or gas will require a Hot Work Permit. There may be other types of work depending on specific locations that may also require a permit. The Hot Work Permit is valid only for the date and shift that is indicated on the permit. When practical material involved in hot work should be moved to a safe location. When a Hot Work Permit is required, please ensure that precautionary measures are taken.

- Gratings and openings will be completely covered to prevent sparks and slag from falling to a level below.
- Fire extinguishers are located in the immediate area of work.
- No flammable or combustible material is stored within 35 feet in any direction, if materials cannot be moved, positive means such as the use of non-combustible shields or fire blankets will be used to confine heat and sparks to prevent them from contacting the combustible material.
- No welding, cutting, or heating will be done where the application of flammable liquids or heavy dust concentrations may create a hazard.
- Fire watch personnel will be identified, trained, and equipped with an extinguisher rated at 20A, 60B:C or greater and will be immediately available in the work area (within 25 feet of all hot work), and remain for a minimum of one hour after hot work has ended to detect and extinguish possible smoldering fires. They will have no other tasks while assigned as fire watch.
- If applicable, any Confined Space Entry procedures will be followed.

Hot Work Permit Process

A Hot Work Permit must be authorized by the Layton Construction Superintendent, or designated person overseeing the project, this permit is available in digital form in BIM360 Field (See Appendix 9 for Hot Work Permit). The person performing the work will review and sign the permit, and keep a copy in the work area. The person giving approval for the permit must ensure that the area is periodically surveyed to ensure that all conditions remain suitable for hot work. Expired Hot Work Permits will be kept on file for at least a month beyond the expiration date (BIM360 Field Hot Work Permits will remain in the system permanently). Each permit will be dated and will carry an expiration time. In the event the hot work will extend past the permit’s expiration time, a new permit must be obtained, or the existing permit extended by the authorized person. The supervisor will be notified when the hot work is complete.

Combustible gas indicators will be calibrated and bump tested prior to performing tests. If the meter is to be used multiple times during the shift, it only needs to be bump tested at the beginning of the shift. The calibration results must be documented on a log book maintained at the job site, or digitally in BIM360 Field.

Fire Watch Procedure

Fire watch personnel will be trained to understand the nature of hot work, and be provided proper PPE to complete their tasks safely. Fire watch will assist in survey of the area to ensure the necessary fire protection equipment is in place and ready for use. Fire watch personnel will remain in constant communication with personnel doing hot work. The fire watch is authorized to stop work whenever they feel the conditions are unsafe, or if the work description on the permit is being exceeded. Assigned fire watch will never leave the area for any reason without a replacement, and remain in the area for at least one hour following the completion of hot work. When bulkheads or walls are involved in hot work, both sides require a fire watch, caution must be used so that heat transfer does not create a hazard.

HOUSEKEEPING

The Layton Construction housekeeping policy is that all equipment, tools, or materials, will be stored, stacked, located, and placed to prevent any incident or injury which could occur in the work area. All work areas will give the direct and obvious impression of a clean and orderly work place. The Layton Nothing Hits the Floor program was initiated to improve productivity, reduce waste and construction debris, improve housekeeping, and increase worker safety on all Layton Construction jobsites. The plan is intended to minimize on-site waste and debris by increasing on-site cleanliness, material organization, and to encourage off-site prefabrication. Implementation of Nothing Hits the Floor will be discussed during the Pre-Mobilization meeting each subcontractor will employ sufficient personnel to maintain a clean and organized work area. Subcontractors will participate, if needed, in a "project wide cleanup effort" to maintain housekeeping of common areas.

Some minimum standards are outlined below for all Layton Construction project sites:

- Debris and loose material will not be placed in an area where winds could blow materials into or off of elevated platforms
- Mud and dirt tracked onto public streets or alleyways will be removed continuously during the workday
- Access walkways, roadways, and fire lanes will not be blocked with material, tools, ladders, scaffolds, welding, leads, air hose, or electrical cords
- Electrical extension cords, light stringers, air hoses, and welding leads will be buried, controlled, elevated above walkways a minimum of seven feet or bridged with the area marked with signage
- Welding rods, nuts, bolts, and washers will be kept in proper containers
- Shackles, slings, chokers, ladders, and safety equipment will be removed from the work area when not in use and stored properly
- Trash containers will be placed at appropriate locations
- All nails will be removed from scrap and lumber or bent over flat to the surface
- Rubbish, trash, and debris will be removed from the work area daily
- Once concrete is poured, work areas will be broom swept at the end of each shift
- Where drinking water is dispensed, an adequate trash container will be located for disposal of drinking cups

LADDERS AND STAIRWAYS

Fall protection while working from a ladder is addressed in the section on Fall Protection.

Stairs or ramps will be provided where there is a change in elevation of 19 inches or greater. Stairways having four or more risers or rising 30 inches or more will have a stair rail system, 36 inches high on each unprotected side. Metal pan stairs will not be used until the pans are filled to prevent a tripping hazard.

Workers will be trained on the safe use of ladders and each ladder is to be inspected and tagged daily prior to use and any ladder that is not in working order will be immediately removed from the project and destroyed. All ladders will be heavy-duty type with a minimum capacity rating of 250 lbs. Ladder landings will remain clear of all obstacles and obstructions to allow easy access on and off the ladder, and ladders will extend past the bearing point no less than 36 inches. When ladders are used to access upper levels, they must be secured to prevent displacement.

Stepladders

Stepladders will only be used with the spreaders fully extended with the spreader bar locked in place. Workers will not stand on the top three rungs of a ladder, or when knees are above the top of the ladder. Stepladders will not be used as straight ladders.

LASERS

All workers that will use a laser will be trained in proper use and hazards associated with lasers. No worker will install, adjust, or operate any laser equipment without a valid qualification card. Standard laser warning signs will be placed around the perimeter of the area the laser is being used. No work will be allowed until all proper signage is in place. No laser equipment will be used that does not contain a label, indicating make, maximum output, and beam spread. Whenever a laser is not in use, shutters or caps will be used and the laser will be turned off. When performing internal alignment, lasers will only be guided by mechanical or electronic means. When environmental conditions exist such as rain, fog, snow, or extremely dusty conditions, use of lasers will not be permitted. Workers using lasers will use appropriate eye protection. No laser beam will be directed at any worker.

MAINTENANCE AND PROTECTION OF TRAFFIC

When it becomes necessary to temporarily close a public street or alley, a written traffic control plan is required showing how the closure will occur and submitted to Layton Construction for review. Refer to the Manual of Uniform Traffic Control Devices (MUTCD) part VI when developing a traffic control plan. At minimum the written Traffic Control Plan will contain the time the street will be required to be closed, a plan illustrating detour routes for traffic impacted by the closed streets, and detailed drawing showing the signage, flaggers, etc. All workers will wear high visibility attire in accordance with the ANSI requirements. Workers assigned as flagmen will be trained as recommended in the Manual of Uniform Traffic Control Devices and state DOT. Work will be stopped if it fails to follow the traffic control plan or occupies a city street or sidewalk without authorization.

MASONRY CONSTRUCTION

A limited access zone is required to be in place prior to the construction of any masonry wall. Masonry walls over eight feet in height will be adequately braced to prevent collapse and remain in place until permanent support is in place. All masons using scaffolds must have scaffold user training and be able to provide documentation if requested by Layton Construction. All scaffolds used in masonry tasks will have adequate handrail protection in the material loading areas. If guardrails are removed to load materials, 100% fall protection must be worn during loading. A Guardrails Removal Permit (see Appendix 7) must be submitted prior to any guardrail removal.

SCAFFOLDING

All scaffolding used on the project will meet the requirements established in Subpart L of OSHA 29 CFR 1926. Each contractor using scaffolds must designate a scaffolding Competent Person to direct and supervise the erection and dismantling of all scaffolding on the project. Scaffolding will be inspected daily by the Competent Person prior to use and the tag signed at the time of inspection. Each trade using the scaffold must designate a Competent Person and they must inspect the scaffold daily prior to any person from that trade using the scaffold. One of the following color-coded scaffold tags will be attached to each scaffold:

- Green Tag – scaffolding is complete and ready for use
- Red Tag – scaffolding is incomplete and not ready for use
- Yellow Tag – scaffolding is usable but personal fall protection is required

Workers required to work from scaffolding will receive training, and have training records available upon request that covers at minimum:

- Nature of any known hazards, such as electrical, fall, or falling objects
- Correct method of erecting, maintaining, and disassembling fall protection systems
- Falling object protection system
- Proper handling of equipment or material on the scaffold
- Maximum load- carrying capacity of the scaffold

Erection

Prior to erection, all scaffolding components will be inspected for defects and any damaged components will not be used, only scaffolding-grade planking will be utilized. Scaffolding will be erected on a firm foundation/footing, and scaffold poles, legs, posts, frame, and uprights will bear on metal base plates and mud sills. Scaffold legs, poles, posts, frames, and uprights will be pinned or locked to prevent uplift. No scaffold will be enclosed unless a qualified engineer designs and approves the attachment to the adjacent structure. Scaffold platforms will be constructed with no space between the platform components. The space between the platform components and the scaffold uprights will not exceed one inch. Because of special circumstances such as building a scaffold around a pipe, the space opening between the scaffold and the object/structure cannot exceed 9 ½ inches. Scaffold planks will extend past the horizontal support a minimum of six (6) inches, but not more than twelve (12) inches, unless cleated or restrained by hooks. Scaffold plank will not be overlapped unless the overlap occurs at a horizontal support, and the minimum planking overlap is twelve (12) inches. Ladders or stairs must be used to access any scaffold platform that is more than two feet above or below the point of access.

End frames of tubular welded scaffold can be used as a ladder if the following criteria are used:

- Specifically designed and constructed as ladder rungs
- Rung length of at least eight inches
- Spacing between rungs not to exceed 16 ¾ inches
- A walk-through frame or gate is provided for access at each landing
- No worker will climb up or down a scaffold using the cross bracing

Workers working below scaffolding will also be protected from falling objects. Scaffold will be equipped with toe plates, screening, debris netting, catch platforms, or a canopy structure.

STEEL ERECTION

No steel erection will begin without a written Notice to Commence Steel Erection (see Appendix 13) from Layton Construction. Workers engaged in steel erection activities including but not limited to connecting, decking, and bolt up are not exempt from Layton Construction's 100% fall protection requirements when working from six (6) feet or greater. Perimeter safety cable installed by steel erector will remain in place unless otherwise instructed by Layton Construction. Training records indicating workers have received required steel erection training will be provided during the pre-mobilization meeting, and if any changes at Site-specific Orientation. These records will be maintained at the project in BIM360 Field and available for review by Layton Construction.

All steel deliveries will be coordinated with the Layton Construction project team to ensure maintenance of traffic around the project. No deliveries will be unbound until inspected and deemed secure by a Qualified Person. Design criteria for any multi-lift device that may be used on the project will be available on the project for review by the Layton Construction Environmental Safety and Health Department. Work will be planned so no load will be swung over the public, other workers, or occupied structures. During bolt-up activities, all steps will be taken to protect workers below from falling objects.

TEMPORARY BARRICADES

Temporary barricades will be erected and maintained to warn or protect workers whenever hazards or processes such as those listed below are encountered on the project. Anyone who enters an identified restricted work area without authorization will be subject to disciplinary action up to and including termination.

- Floor or wall openings
- Working above other workers
- Open excavations/trenches
- Unguarded equipment
- Overhead loads
- Closed stairwells
- Exposure to vehicular traffic
- Startup operations and testing of equipment/systems
- Process hazards such as discharges, open systems, etc.

When barricading is required, “Caution” or “Danger” tape should be installed at least 15 feet from excavations, trenches, holes, leading edges, and floor or wall openings. Install a standard “Caution” or “Danger” tag that identifies the hazard at regular intervals around the barricaded area including the name and contact information of the Competent Person that erected the barricade. Temporary barricades will not impede stairs, walkways, driveways, or aisles without approval from Layton construction project team, and identification of alternative passageways is determined. The following guidelines in determining type of Temporary barricades will be followed:

- **Yellow “Caution” Tape** is used to limit the passage through the barricaded area. This barricading should only be used to protect from hazards that are not severe or when the potential for severe injury or death is unlikely
- **Red “Danger” Tape** is used to prohibit the passage through the barricaded area. This barricading should be used to protect from hazards that have the potential to cause serious injury or death. Red Danger tape is **NOT a substitute for a guard rail**. Danger tape is not to be used if the hazards cannot be eliminated or removed during a single work shift. Danger tape should always be approved by the Layton Construction Superintendent

When rigid barricading is required, it should support and maintain construction fencing to prevent tipping or sagging. If there is a danger of vehicles or heavy equipment striking the barricade pins should be installed in concrete barriers. There should be adequate access to the work area, and once the work is complete and the hazard is eliminated the rigid barricade will be removed immediately.

- **Rigid Barricades** are used when protection is required beyond a single work shift. It will be used to protect workers from unguarded moving machinery/equipment, vehicular or heavy equipment traffic and low light conditions. Rigid barricading will consist of standard guardrail, temporary chain link fencing, tube and coupler scaffold members with construction fencing attached, or concrete barriers

TILT UP PANEL CONSTRUCTION PROCEDURE

General Requirements

The nature of tilt-up construction dictates the need for thorough pre-planning. The economy and success of tilt-up construction is realized by an efficient on-site production operation with each step of the construction sequence building on the previous step. The erection of the wall panels is the most important phase of tilt-up construction. It is critical for the engineers and contractors to plan and review this process completely and thoroughly. Construction documents will be submitted to a third-party lift engineer for review and approval. The QA panel check off form will be used for documentation.

Slab as a Work Platform

The quality of the floor slab in a tilt-up constructed building is extremely important. The tilt-up panels are normally cast on the floor slab of the building and any imperfection in the floor slab will be mirrored in the panel. For best results, the floor slab should have a hard, dense, steel trowel surface. Slab thickness and compressive strength must meet bracing designs. You may have to pour a thickened slab at brace locations.

Bond Breaker and Curing Compounds

Bond breakers and curing compounds are among the most critical materials used on a tilt-up project. These products should have their performance criteria carefully evaluated. The application of the curing compound on the floor slab is one of the critical steps in the preparation process. Check the slab and bond breaker before pouring any concrete. The slab should have a slightly tacky, soapy feeling. Bond breaker can be tested by dropping a small amount of water on the casting bed, from two feet above to allow it to splatter. If the bond breaker is applied correctly, the water will bead into small droplets as it would on a freshly waxed automobile. If the water does not bead, re-spray all of the suspected areas of the casting slab. Whenever there is doubt about sufficient bond breaker on the casting slab, always apply more. It is the cheapest insurance available for as successful tilt-up job.

TILT UP PANEL ERECTION PROCEDURE

Preparation for Lifting

Clean the panel and the surrounding floor slab area. Locate and prepare all pertinent embedded devices that are accessible. Do any dressing or patching that can be accomplished on the ground. Attach all pipe braces and strong backs as required. Each panel should be numbered and clearly identified according to the panel layout/erection sequence plan.

Place the identifying mark in a position that will not be exposed when the structure is completed. Mark locations and heights of all shims in case they are displaced. The structure footing should also be marked with the corresponding identifying numbers to give the erection crew clear indication where each panel goes. The footing should be appropriately marked to show the proper position of each panel on the footing. All lifting inserts should be uncovered, cleaned out and tested with a hardware unit several days prior to erection day. Rotary hammers, drills, leveling shims, cutting torch, steel wedges, pry bars, level and plumb bob, and full set of hand tools will be available at the job site. Have a set of back up tools onsite. For larger panels, you may need a port-a power for alignment. Verify concrete compressive strength at time of initial lift is at least the strength listed in the insert selection chart for the insert being used. Have additional cylinders cast on your last tilt panel pour.

Crane Classification

Cranes selected for tilt-up projects will be properly certified. Contractors will make certain that they have documentation available at the job site attesting to the crane's certification.

Equipment and Crew

The erection contractor must itemize the rigging and equipment required for a proper and safe lift. The erection details supplied by the lift engineer will specify all rigging configurations and cable lengths required for the project. These details are an integral part of the erection stress calculations and should be strictly adhered to. The reaction details will specify the diameter and safe working load of the rigging cables. All crews will complete and train on panel construction through the job hazard analysis process.

Day of Erection Safety Meeting

A full crew Pre-Task Plan safety meeting will be held each day prior to lifting, where all pertinent safety details are discussed and all questions answered. Reinforce the need for all concerned to be alert during lifting. Only members of the erection crew will be allowed in the area. The Rigger Foreman will be identified at the safety meeting, this individual will be the one the crane operator looks to for all signals during the lifting process. The Rigger Foreman must be experienced with handling panels and be familiar with the precise set of hand and arm signals to communicate with the crane operator. During the safety meeting, the Rigger Foreman should demonstrate the proper use of the lifting hardware and bracing hardware, and how to use any necessary tools or equipment.

Prior to Lifting

Check wind conditions prior to lifting a panel. Make sure the area is clear of spectators. Inspect all panels for projections (such as rebar) that may interfere with the process. Inspect all rigging and hardware for alignment and be sure that the rigging is free of snags. If non-swivel sheaves are being used, make certain the sheaves are properly aligned. Braces are usually attached to the panels prior to lifting, be sure that the braces will not be trapped by the rigging during the lift. Be alert for panels sticking to the casting bed. Carefully positioned pry bars and/or wedges at the insert lines can often help the cranes successfully release the panels from the casting bed.

During the Lift

As the cables are being tensioned, they invariably tend to twist and rotate the hardware. Twisting the hardware can cause side loading. The rigging crew needs to be alert for this condition and halt the lift to realign the hardware. It is the Rigger Foreman's responsibility to be alert to any obstacles in the path of the panel and crew.

Plumbing the Panels

Make certain that the panels being plumbed does not strike a previously erected panel or panel bracing. Keep the area surrounding the panel clear of workers until the panel is firmly braced. If the panel being plumbed is a closure panel, take exact measurement prior to lifting to be sure the panel will fit. Tilt-up panels should be as plumb as possible prior to attaching the bracing to the floor slab. Temporarily out-of-plumb should not exceed 4" at the top of the panel. Fine tuning of the panel to be plumb before releasing the crane. When the panel is going to support an adjacent spandrel or lintel panel. The supporting panels need to be accurately placed in their exact position to prevent the need of adjusting them after placement of the spandrel or lintel panel. When the bracing design specifies a subsequent system of knee, lateral, and end or cross bracing. Attempts to adjust a panel after subsequent bracing is in place would necessitate loosening or removing the bracing, putting the panel and workers in a dangerous position.

Bracing Panels

All bracing should be in place and complete before relaxing the crane load. The crane load should be released slowly. Do not release the crane load if for any reason, the bracing does not appear to be adequate. Bracing anchors must be installed per manufacturer's instructions. Do not use wedge anchors for braces. Bracing will be monitored daily with special attention after high winds, always check the tightness of bolts. Bolted hardware must have full bearing on the concrete surface and attachment bolts bear fully on the hardware. Caution must be taken so that the hardware is not subjected to a side loading that will cause an additional unintended loading. Coil bolts must have a minimum coil penetration through the insert coil but are not bearing on concrete at the bottom of the void. There are instances when the crane's position will prevent the lateral bracing from being completed. Once the crane has cleared the area, the lateral and end bracing can be completed. This should be accomplished as soon as possible, no more than one panel behind the erection crew. Bracing on erected panels must be completed at the end of the work day.

After the Lift

When constructing the floor slab, a perimeter strip, generally three to five feet wide is often open to facilitate the footing excavation. This excavation area can be up to five or six feet deep, depending on the building design, and won't be backfilled until after the wall panels have been erected. The perimeter strip must be backfilled and compacted very carefully to avoid movement or bending of the panel. Wall braces should never be removed until all structural connections are complete. Note that the perimeter strip between the floor slab and the wall panels is considered a structural connection. If the building's structural drawings do not indicate when the braces can be removed the engineer of record will be consulted.

WELDING AND CUTTING

When burning or welding using compressed gases, flame arrestors will be installed on both the torch side and regulator side of the oxygen and gas hoses.

Arc Welding and Cutting

Welding current return circuits or grounds must carry their current without hot or sparking contacts and without passage of current through equipment or structures. Specifically, welding current must not be allowed to pass through any of the following materials:

- Acetylene, fuel gas, oxygen, or other compressed gas cylinders
- Tanks or containers used for gasoline, oil or other flammable or combustible material
- Pipes carrying compressed air, steam, gases or flammable or combustible liquids
- Conduits carrying electrical conductors
- Chains, wire ropes, metal hand railings, or ladders, machines, shafts, bearings, or weighing scales

Whenever practical, all arc welding and cutting operations will be shielded by non-combustible or flame-proof screens. Screens will be mandatory when arc welding or cutting creates exposure for other crafts or individuals. The ground for the welding circuit will be mechanically strong and electrically adequate for the service required and should be attached directly to the work piece. When possible, electrode and ground cables will be supported to prevent obstructions interfering with the safe passage of workers. Cables with worn insulation may not be used.

Gas Welding, Cutting, and Soldering

A suitable cylinder cart, chain, or other secure non-flammable fastening should be used to keep cylinders from being knocked over while in use. Cylinders of oxygen will not be stored next to cylinders of acetylene or other fuel gas. They will be separated by 20 feet or by non-combustible barrier with ½ hour fire rating. Oxygen cylinders, cylinder valves, couplings, regulators, hose and apparatus will be kept free of and away from oil and grease. Oil or grease in the presence of oxygen under pressure may ignite violently. Empty cylinders will have their valves closed. Valve protection caps will always be in place except when cylinders are in use or connected for use. Compressed gas cylinders, empty or full will be secured in an upright position at all times. Empty cylinders should be marked EMPTY or MT for identification. Regulators and hoses will be frequently inspected for leaks, worn places and loose connections. Regulators will also be checked for operable gauges. Approved flash arresters will be provided in both oxygen and acetylene hoses at the regulator connection.

FORMS APPENDIX

APPENDIX 1:	LAYTON INCIDENT REPORT FORMS (EMPLOYEE, SUPERVISOR, WITNESS)
APPENDIX 2:	COMPETENT PERSON FORM
APPENDIX 3:	CONFINED SPACE ENTRY PERMIT
APPENDIX 4:	DAILY PRE-TASK PLAN
APPENDIX 5:	ENERGIZED WORK / ARC FLASH PERMIT
APPENDIX 6:	EXCAVATION PERMIT
APPENDIX 7:	GUARD RAIL REMOVAL PERMIT
APPENDIX 8:	HARNESS AND LANYARD INSPECTION
APPENDIX 9:	HOT WORK PERMIT
APPENDIX 10:	CRITICAL LIFT CHECKLIST FORM
APPENDIX 11:	LOCKOUT/TAGOUT CHECKLIST
APPENDIX 12:	MONTHLY INSPECTION COLOR CODE SIGN
APPENDIX 13:	NOTICE TO COMMENCE STEEL ERECTION
APPENDIX 14:	PRE-MOBILIZATION MEETING AGENDA
APPENDIX 15:	SCAFFOLD TAGS
APPENDIX 16:	SILICA STANDARDS – TABLE 1
APPENDIX 17:	UTILITY PROTECTION PERMIT
APPENDIX 18:	NOTICE OF NON-COMPLIANCE

EMPLOYEE INCIDENT REPORT**Employee Incident Report**☐ Layton Construction☐ Subcontractor

Project Name: _____ Project Number: _____

Where on Project did Incident Occur? _____

Date of Incident: _____ Time of Incident: _____ Date of Report: _____

Name of Company: _____

Employee's Name: (First, Middle, Last): _____

Birthdate: _____ Age: _____ Social Security Number: _____

Street Address: _____

City, State Zip: _____ Phone Number: _____

Marital Status: ☐ Married ☐ Single ☐ Divorced # of Dependents: _____

Job Title: _____ Years of Experience: _____

Hire Date: _____ State Hired In: _____ Hourly Wage: _____

Full Time ☐ Part Time ☐ Supervisors Name: _____

Time Shift Began: _____ Date/Time asked for medical attention: _____

Circle the Answers Below:

Scope Specific Safety Plan completed? Yes No

All Hands Huddle Attendance Yes No

Stretch & Flex Performed? Yes No

Pre-Task Plan completed? Yes No

Number of Hours Worked Prior to Incident

Week	# of Hours Worked
Day of Incident	
Last Week	
Previous Week	
Previous Week	
Previous Week	

Body Part Injured: _____

Task being performed: _____

Description of Incident: What Happened? _____

What could have been done to prevent this Incident? _____

Names of Witnesses: _____

Signature of Employee: _____ Date: _____

<https://my.laytoncompanies.com/shared documents/safety/2017safety forms/employee incident report>

Revised 1/2019

SUPERVISOR INCIDENT REPORT**Supervisor Incident Report**☐ Layton Construction☐ Subcontractor

Project Name: _____ Project Number: _____

Location of Incident on Project: _____

Date of Incident: _____ Time of Incident: _____ Date of Report: _____

Name of Company: _____

Employee's Name: (First, Middle, Last): _____

LCC Supervisor's Name: _____

Subcontractor Supervisor Name: _____

Craft Type: _____ # Years of Experience: _____

Circle the Answers Below:

Where was the Employee treated? Clinic ER
 Medical Status: FA REC REC/R LTA
 Was Safety Equipment Provided? Yes No
 Was Safety Equipment Being Used? Yes No
 Pre-Task Plan Completed Day of Yes No
 Scope Safety Plan Completed? Yes No

**Number of Hours Worked 4
Weeks Prior to Incident**

Week	# of Hours Worked
Last Week	
Previous Week	
Previous Week	
Previous Week	

Task being performed: _____

Description of Incident: _____

Cause of Incident: _____

Proposed Corrective Action: _____

Is the Incident Questionable? State Reason: _____

Signature of Supervisor: _____ Phone Number _____

WITNESS STATEMENT REPORT

Witness Statement Report



Witness is employed by: ☐ Layton Construction

☐ Subcontractor

Project Name: _____ Project Number: _____

Employee's Name Involved in the Incident: _____

Name of Company: _____

Witness Name: _____ Phone Number: _____

Witness Address: _____

City, State Zip: _____

DESCRIPTION OF INCIDENT:

Location of Incident on Project: _____

Date of Incident: _____ Time of Incident: _____ Date of Report: _____

Who was involved: _____

What Happened? _____

Why? What or Who Caused the Incident? _____

Signature of Witness: _____ Date: _____

COMPETENT PERSON FORM*2020 | Layton Construction Company LLC***DESIGNATED COMPETENT PERSON ACKNOWLEDGEMENT FORM****Project Name:** _____ **Project #:** _____**Purpose**

The purpose of this procedure is to define and list the areas within 29 CFR 1926, OSHA's Construction Standards, where a Competent Person is required to be a part of a particular project activity.

Definition

A Competent Person is someone who, by reason of education, training, and experience, is capable of identifying existing and predictable hazards in the surrounding or working conditions which are unsanitary, hazardous, or dangerous to employees, and who has authorization to take prompt corrective measures to eliminate them. The training records and documentation will be submitted with this form at the pre-mobilization meeting.

Responsibility

The designated Competent Person is responsible for recognizing and correcting safety hazards specific to the area of competency. This person has the authority to stop work in the event of any potential safety concern on the job site. This representative is considered the contact person for Layton Construction on safety related issues. This form must be completed by the subcontractor and the subcontractor's designated Competent Person(s). Where a subcontractor is responsible for multiple crafts, it is necessary to maintain additional designated Competent Persons and forms for each additional tier. This form must be updated any time there is a change in the designated representative(s). This designated person must be on the project site whenever the area of competency is functioning.

Acknowledgement

I, _____ representing _____, have assigned the below listed
Subcontractor Supervisor (Print) (Company Name)

personnel to be the Competent Person(s) in the areas indicated and I acknowledge that this individual has been thoroughly trained and is experienced in hazard recognition and has the authority to stop work and correct hazards in the event of a potential hazardous or imminent danger situation.

(Subcontractor Supervisor Signature)Date**Area of Competency****a. Project Competent Person (Safety Representative)**

- | | | |
|-----------------------------|-------------------------|---------------------------------|
| b. Asbestos | k. Electrical | t. Materials / Personnel Hoists |
| c. Accident Prevention | l. Excavations/Trenches | u. Mechanical Demo |
| d. Bolting/Riveting/Fitting | m. Fall Protection | v. Respiratory Protection |
| e. Caissons/Cofferdams | n. First Aid/CPR | w. Scaffolding |
| f. Concrete/Forms/Shoring | o. Hearing Protection | x. Slings |
| g. Compressed Air | p. Ionizing Radiation | y. Tilt Panel Operations |
| h. Confined Space Entry | q. Ladders | z. Tunnels/Shafts |
| i. Cranes/Derricks | r. Lead | aa. Underground Construction |
| j. Demolition | s. Lift Slab Operations | bb. Welding / Cutting |

I acknowledge that I have been thoroughly trained and have the experience to perform the duties as a Competent Person in the areas indicated above. I understand that I have the responsibility and authority to correct hazards and to stop work in the event of a potential hazardous or imminent danger situation.

Competent Person (Signature)	Competent Person (Print Name)	Areas of Competency <small>List letter(s)</small>	Date
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____



LAYTONCONSTRUCTION.COM



CONFINED SPACE ENTRY PERMIT

2020 / Layton Construction Company LLC

CONFINED SPACE ENTRY PERMIT

DESCRIPTION – REQUIRED FOR ALL ENTRIES					
Permit #:		Subcontractor:			
Supervisor:		Location:			
Type:	<input type="checkbox"/> Non-Permit	<input type="checkbox"/> Permit	Date and Time of Entry:		AM/PM
Location of Confined Space:					
Type of Confined Space:	<input type="checkbox"/> Tank	<input type="checkbox"/> Pipe	<input type="checkbox"/> Manhole	<input type="checkbox"/> Tunnel	<input type="checkbox"/> Vault
Other: <input type="checkbox"/>					
Work Description/Purpose of Entry:					
Hazards:					
VERIFICATIONS – REQUIRED FOR ALL ENTRIES					
Lockout/Tag out (electrical, mechanical, hydraulic, etc.)		Date		Entry Supervisor's Initials	
Purged, Cleaned, Drained, and Ventilated					
Employee Training					
	Required	Verified		Required	Verified
Safety Department Notified	X	<input type="checkbox"/>	Authorized Entry Log at Access	<input type="checkbox"/>	<input type="checkbox"/>
Adequate Access	X	<input type="checkbox"/>	Fire Extinguisher Available	<input type="checkbox"/>	<input type="checkbox"/>
Adequate Lighting (low voltage)	X	<input type="checkbox"/>	Attendant	<input type="checkbox"/>	<input type="checkbox"/>
Harness / Lifelines	X	<input type="checkbox"/>	Warning Signs Posted at Access	<input type="checkbox"/>	<input type="checkbox"/>
Training	X	<input type="checkbox"/>	Respirators Required? If required, what type?	<input type="checkbox"/>	<input type="checkbox"/>
Ventilation Adequacy	X	<input type="checkbox"/>	Protective Clothing Required (describe)	<input type="checkbox"/>	<input type="checkbox"/>
Communications Equipment	X	<input type="checkbox"/>	Rescue Equipment/Service Available (Tripod/winch or emergency services)	<input type="checkbox"/>	<input type="checkbox"/>
Continuous Air Monitoring	X	<input type="checkbox"/>	Hot Work Permit Required	<input type="checkbox"/>	<input type="checkbox"/>

Attach a separate log if more entrants are involved in permit required confined space activity than allowed for on this form.

Attendant(s) Name(s): 	Entrant(s) Name(s): 						
AIR MONITORING – REQUIRED FOR ALL ENTRIES							
Make:		Model:		ID#			
Field Calibration Date:		Calibrated By:					
Atmosphere Checked By:							
Contaminants	Permissible Levels	1 st Check*	Time	2 nd Check*	Time	3 rd Check*	Time
% Oxygen (O ₂)	19.5% to 23.5%						
LEL	Less than 10%						
Carbon Monoxide (CO)	Less than 35 ppm						
Hydrogen Sulfide (H ₂ S)	Less than 10 ppm						
Other:							
* 1 st CHECK TO BE COMPLETED PRIOR TO ENTRY							
IN CASE OF EMERGENCY, CALL:				OR			
AUTHORIZATION							
Entry Supervisor:				Date:			

DAILY PRE-TASK PLAN

Date: _____

Company: _____

Yes/No 1- Work area has been walked by supervisor to identify safety concerns. (i.e., material handling, ladders, access/egress, fall protection, work surfaces, etc.)

Yes/No 2- Work has been coordinated with other subcontractors in the area: Company: _____

Yes/No 3- Are tools, materials, and equipment available and in safe and good condition, inspected? Color code _____

Yes/No 4- Has all necessary training for this task been completed and all new employees familiarized with work area? If No, Stop & Complete

Yes/No 5- Sufficient personnel have been assigned to complete this task safely. If No address what you will do? _____

PERMITS: Check all that apply ☐ Confined Space ☐ Excavation ☐ Hot Work ☐ Utility Protection ☐ _____

HAZARD ASSESSMENT: CHECK ALL THAT APPLY AND DISCUSS

<input type="checkbox"/> Access/ Egress	<input type="checkbox"/> Ladders	<input type="checkbox"/> Material Handling	<input type="checkbox"/> Falls
<input type="checkbox"/> Trenching & Excavation	<input type="checkbox"/> Pinch Points	<input type="checkbox"/> Body Placement / Stability	<input type="checkbox"/> Slips / Trips
<input type="checkbox"/> Reaching/Bending/Twisting	<input type="checkbox"/> Repetitive Motion / Vibration	<input type="checkbox"/> Housekeeping	<input type="checkbox"/> Lifting / Pulling / Pushing
<input type="checkbox"/> Other: _____			

[illegible]

<i>Print Name</i>	<i>Signature</i>	<i>Print Name</i>	<i>Signature</i>

Signature of Supervisor

57

APPENDIX 4

PLANIAMENTO DIARIO DE TRABAJO

Dia: _____

Empresa: _____

Antes de empezar su deber, o cuando circunstancias y condiciones cambien comunque los siguiente

Si/No	1-La area de trabajo ha sido inspeccionada por el supervisor e identificado riesgos (i.e., manejo de materiales, escaleras, acceso/salidas, proteccion contra caidas.plataforma de trabajo. etc.)
-------	---

Si/No 2-Ha coordinado el area de trabajo con otras empresas: Empresa: _____

Si/No 3-Tiene disponibles herramientas, materiales y maquinaria que estan en buenas condiciones e inspeccionadas ? Color del mes _____

Si/No 4-Tienen el entrenamiento necesario para realizar esta tarea y estan familiarizados con el trabajo? Si No, Pare & Expliqueles

Si/No 5- Ha asignado suficiente personal para completar esta tarea de forma segura. Si No Explique: _____

PERMISOS: Marque lo aplicable ☐ Espacios confinados ☐ Excavacion ☐ Fuego / Chispas ☐ Proteccion de Utilidades

EVALUACION DE RIESGOS: MARQUE LO APLICABLE Y DISCUTALO

<input type="checkbox"/> Accesos/ Salidas	<input type="checkbox"/> Escaleras	<input type="checkbox"/> Manejo de Material	<input type="checkbox"/> Caídas
<input type="checkbox"/> Zanjas & Excavaciones	<input type="checkbox"/> Posibles Machucones	<input type="checkbox"/> Posicion del cuerpo / Estabilidad	<input type="checkbox"/> Resbalones / Tropezones
<input type="checkbox"/> Alcance/Flexion/Tregiversar	<input type="checkbox"/> Movimientos Repetitivos / Vibraci	<input type="checkbox"/> Limpieza	<input type="checkbox"/> Levantando / Jalando / Empujando
<input type="checkbox"/> Otros: _____			

[illegible]

Asistencia:

Imprima Nombre

Firma

Imprima Nombre

Firma

Imprima Nombre del Supervisor

Firma del Supervisor

Rev. 8/2019

ENERGIZED WORK PERMIT**2020 | Layton Construction Company LLC**
ENERGIZED WORK PERMIT

An Energized Work Permit must be submitted for approval whenever work is to be performed on energized circuits. **Part 1** of this permit is to be completed by the Authorized Person, and reviewed and signed by the Safety Manager and/or the Client's Representative.

Job Name: _____ Job # _____ Today's Date: _____
 Work Area: _____ Start Date: _____ Completion Date: _____
 Scope of Project / Equipment information: _____

Shutdown Requested: ☐ Yes ☐ No Shutdown Approved: ☐ Yes* ☐ No**
 *Lock out / Tag out Procedures for a Zero Energy State will be used ☐ Yes (If not checked do not proceed)
 **Reason for non approval: _____
 Signature of Client/Customer _____ Date: _____
 Signature of Jobsite Foreman _____ Date: _____

Part 2 of this permit to be completed by the Safety Manager before work commences, if Shutdown request is not approved.

Equipment Voltage: ☐ 50 Volts or less ☐ 51V to 250 Volts ☐ 251V to 600V ☐ Over 600 Volts

Supervisors in charge of project: _____

Employee's performing work: _____

Required Protective Equipment: ☐ Category 1 Clothing (4 cal/cm²) ☐ Category 2 Clothing (8 cal/cm²) ☐ Category 2* Clothing (8 cal/cm²)
☐ Category 3 Clothing (25 cal/cm²) ☐ Category 4 Clothing (40 cal/cm²) ☐

Additional Protective Equipment: ☐ Voltage Tools ☐ Voltage Gloves ☐ Voltage Meters ☐ Blankets & Mats

Means of restricting access of unqualified persons from work area: _____

Is the fault energy level available at the location equal to or less than the table 130.7(C)(9)notes? ☐ YES ☐ NO
 If "NO" Flash Energies could be higher than expected.

Additional Check List:

	YES	N/A
was a Job Briefing to discuss Job-specific Hazards performed (JSA / Risk Assessment)?	<input type="checkbox"/>	<input type="checkbox"/>
Are Supervisors/Employee's Task Trained for Arc-Flash Protection and Hot Work?	<input type="checkbox"/>	<input type="checkbox"/>
Are line tools and voltage gloves dated for current testing date?	<input type="checkbox"/>	<input type="checkbox"/>
Were tools and voltage gloves inspected and field tested before use?	<input type="checkbox"/>	<input type="checkbox"/>
Has the work area been adequately barricaded and warning signs posted?	<input type="checkbox"/>	<input type="checkbox"/>
Are Lock and Tags in place for each employee were possible?	<input type="checkbox"/>	<input type="checkbox"/>
Are all safety warnings adhered to?	<input type="checkbox"/>	<input type="checkbox"/>
Are all Protective guards left in intact were possible?	<input type="checkbox"/>	<input type="checkbox"/>

Determine Approach Boundary from NFPA 70E, Table 130.2 (C):
☐ Limited Approach ☐ Restricted Approach ☐ Prohibited Approach

Flash Protection Boundary (distance a maximum of a 2nd degree burn could occur) NFPA 70E Table 130.3(A)* ☐

*Voltage levels between 50 & 600 Volts the flash boundary shall be 4 feet (48") based on the product of clearing time of 2 cycles (0.033 sec) and the available bolted fault current of 50 kA or any combination not exceeding 100 kA (1667 ampere seconds)

Comments: _____

Authorized Person _____ Signature _____ Print Name _____ Date: _____

EXCAVATION PERMIT**2020 / Layton Construction Company LLC
EXCAVATION PERMIT**

Location: _____

Permit #: _____ Date: _____

Company Name: _____ Shift: _____

Excavation Location: _____

Excavation Length _____


Width & Depth: _____

Soil Classification: ☐ Type A
☐ Type B
☐ Type C

Protective System Used: ☐ Yes ☐ No Type: ☐ Shielding (Box) ☐ Sloping
☐ Shoring ☐ Benching
☐ Other: _____

Weather: _____

Competent Person: _____ Person Completing Report _____



NOTE: Trenches over 4 feet deep will use a protective system.

EXCAVATION REQUIREMENTS			
YES	NO	N/A	GENERAL
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Protective system used in any trench/excavation greater than 4 feet deep
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Spoils, materials & equipment set back ≥ 2 feet from the edges of the excavation
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering designs for sheeting and/or manufacturer's data on trench box capabilities on site
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Adequate signs posted and barricades provided
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Employee training conducted prior to beginning work
YES	NO	N/A	UTILITIES
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Utility company contacted & given 24 hours' notice &/or utilities already located & marked
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Utility locations (overhead & underground) reviewed with operator & employees
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Utilities protected, supported or removed when excavation opened
YES	NO	N/A	WET CONDITIONS
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Employees protected from water accumulations (continuous dewatering)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Inspection made after every rainstorm
YES	NO	N/A	HAZARDOUS ATMOSPHERES
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Air monitored for methane gas prior to entering trench/excavation
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Air monitoring & ventilation provided for potentially hazardous atmospheres
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Emergency equipment available where hazardous atmospheres could or do exist
YES	NO	N/A	ENTRY & EXIT
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Ladders no further than 25 feet from ANY employee in ANY direction
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Ladders extend 3 feet above excavation edge and secured
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Wood ramps constructed of uniform material thickness and cleated together at bottom
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Employees protected from cave-ins where entering/exiting the excavation

NOTE: Items marked NO below MUST be corrected prior to any employee entering the excavation.

APPROVAL

Layton Construction Project Manager/Superintendent: _____ Date: _____

GUARDRAIL REMOVAL PERMIT*2020 / Layton Construction Company LLC***GUARDRAIL REMOVAL PERMIT**

Work will not be performed until this form is approved by Layton Construction Project Team.

Contact Information:

Contractor: _____ Date: _____

Foreman's Name: _____ Foreman's Phone #: _____

Write out specific Location N, S, E, W include grid (if known), and Level 1 (Level 1, Level 2, etc.)LocationLevel

_____	_____
_____	_____
_____	_____

Employee(s) Performing WorkNameSignature

_____	_____
_____	_____
_____	_____
_____	_____

Considerations

Reason for cable being dropped / removed? _____

Number of spans being affected? _____

What other contractors are working in the area? _____

Total length of cable affected? _____

How will you continually notify other contractors? _____

Amount of time cable will be down: _____

Fall Protection Plan

If "No" is the answer to any of the questions below, the Layton Construction ESH Department must be contacted for review prior to guardrail removal.

Does your company have a fall protection program? Yes No

Have workers performing work been trained in Fall Protection? Yes No

Has fall protection been put in place? Yes No

Will workers be tied off within 15 feet of down cable? Yes No

Describe how workers will be tied off: _____

Describe how the other trades will be protected from fall hazards: _____



LAYTONCONSTRUCTION.COM



Revised 1/2020

HOT WORK PERMIT

2020 / Layton Construction Company LLC
HOT WORK PERMIT

ISSUED TO:		CONTRACTOR:		PERMIT #:									
DATE AND TIME TO BE USED:		EXPIRATION DATE AND TIME:											
LOCATION TO BE USED:													
SCOPE OF WORK:													
<u>FIRE PROTECTION</u> (REQUIRED, IF CHECKED) <table style="width: 100%; border: none;"> <tr> <td><input type="checkbox"/> FIRE EXTINGUISHERS</td> <td><input type="checkbox"/> AREA WET DOWN</td> </tr> <tr> <td><input type="checkbox"/> SEWERS AND DRAINS COVERED</td> <td><input type="checkbox"/> CHARGED FIRE HOSE</td> </tr> <tr> <td><input type="checkbox"/> SPARK CONTAINMENT</td> <td><input type="checkbox"/> FLAMMABLES / COMBUSTIBLES REMOVED / COVERED</td> </tr> <tr> <td><input type="checkbox"/> MSDS REVIEWED</td> <td><input type="checkbox"/> FIRE WATCH *(REQUIRED FOR 1 HOUR AFTER WORK ENDS)</td> </tr> </table> * NAME OF FIRE WATCH: _____						<input type="checkbox"/> FIRE EXTINGUISHERS	<input type="checkbox"/> AREA WET DOWN	<input type="checkbox"/> SEWERS AND DRAINS COVERED	<input type="checkbox"/> CHARGED FIRE HOSE	<input type="checkbox"/> SPARK CONTAINMENT	<input type="checkbox"/> FLAMMABLES / COMBUSTIBLES REMOVED / COVERED	<input type="checkbox"/> MSDS REVIEWED	<input type="checkbox"/> FIRE WATCH *(REQUIRED FOR 1 HOUR AFTER WORK ENDS)
<input type="checkbox"/> FIRE EXTINGUISHERS	<input type="checkbox"/> AREA WET DOWN												
<input type="checkbox"/> SEWERS AND DRAINS COVERED	<input type="checkbox"/> CHARGED FIRE HOSE												
<input type="checkbox"/> SPARK CONTAINMENT	<input type="checkbox"/> FLAMMABLES / COMBUSTIBLES REMOVED / COVERED												
<input type="checkbox"/> MSDS REVIEWED	<input type="checkbox"/> FIRE WATCH *(REQUIRED FOR 1 HOUR AFTER WORK ENDS)												
<u>SITE WORK CHECKLIST</u> <table style="width: 100%; border: none;"> <tr> <td><input type="checkbox"/> COMBUSTIBLES PROTECTED*</td> <td><input type="checkbox"/> PURGE**</td> </tr> <tr> <td><input type="checkbox"/> COMBUSTIBLES RELOCATED</td> <td><input type="checkbox"/> VENTILATION</td> </tr> <tr> <td><input type="checkbox"/> LOCKOUT / TAGOUT</td> <td><input type="checkbox"/> VALVES CLOSED</td> </tr> <tr> <td><input type="checkbox"/> MSDS REVIEWED</td> <td><input type="checkbox"/> WATER WASH</td> </tr> </table> ** GAS USED FOR PURGING: _____ * PROTECTION METHOD: _____						<input type="checkbox"/> COMBUSTIBLES PROTECTED*	<input type="checkbox"/> PURGE**	<input type="checkbox"/> COMBUSTIBLES RELOCATED	<input type="checkbox"/> VENTILATION	<input type="checkbox"/> LOCKOUT / TAGOUT	<input type="checkbox"/> VALVES CLOSED	<input type="checkbox"/> MSDS REVIEWED	<input type="checkbox"/> WATER WASH
<input type="checkbox"/> COMBUSTIBLES PROTECTED*	<input type="checkbox"/> PURGE**												
<input type="checkbox"/> COMBUSTIBLES RELOCATED	<input type="checkbox"/> VENTILATION												
<input type="checkbox"/> LOCKOUT / TAGOUT	<input type="checkbox"/> VALVES CLOSED												
<input type="checkbox"/> MSDS REVIEWED	<input type="checkbox"/> WATER WASH												
<u>GAS MONITORING REQUIRED</u> <input type="checkbox"/> YES <input type="checkbox"/> NO													
<u>TYPE</u>	<u>TIME</u>	<u>%LEL / PPM</u>	<u>TESTER</u>										

LAYTON AND CONTRACTOR SUPERVISOR ISSUING PERMIT, DATE AND INITIAL IN APPROPRIATE BOX:											
MON ____/____/____		TUE ____/____/____		WED ____/____/____		THUR ____/____/____		FRI ____/____/____		SAT ____/____/____	
L	C	L	C	L	C	L	C	L	C	L	C

HOT WORK IS AUTHORIZED BY: _____

PERSON RESPONSIBLE FOR HOT WORK SAFETY: _____

THIS PERMIT IS AUTHORIZED FOR ONE SHIFT ONLY (UNLESS OTHERWISE NOTED) AT THE DATE, TIME AND LOCATION SHOWN ABOVE.

RETURN THIS PERMIT WHEN WORK IS COMPLETED TO LAYTON SAFETY.

CRITICAL LIFT PLAN

Form 16-3 CRITICAL LIFT PLAN				
For use of this form, see EM 385-1-1, Section 16. Proponent is Crane HHWG.				
Date:		Prepared By:		
Location:		USACE District:		
<i>A "critical lift" is defined as any non-routine crane lift requiring detailed planning and additional or unusual safety precautions. Critical lifts include: lifts made where the load weight is greater than 75% of the rated capacity of the crane; lifts which require load to be lifted, swung or placed out of the operator's view; lifts made with more than one crane; lifts involving non-routine/technically difficult rigging arrangement; hoisting personnel with a crane or derrick; or any lift which the crane operator believes should be critical.</i>				
A. TOTAL LOAD		E. CRANE PLACEMENT <i>(Mobile Cranes Only)</i>		
1. Load Weight	<input style="width: 100%;" type="text"/>	lbs	1. Maximum Bearing Pressure <input style="width: 100%;" type="text"/> PSF	
2. Wt. of Aux. Block	<input style="width: 100%;" type="text"/>	lbs	<small>Note: Bearing Pressure Calculations must be attached on Page 3.</small>	
3. Wt. of Main Block	<input style="width: 100%;" type="text"/>	lbs	2. Ground Conditions Suitable for Load? <input style="width: 100%;" type="text"/> YES / NO	
4. Wt. of Lifting Beam	<input style="width: 100%;" type="text"/>	lbs	<small>Note: Ground Condition Calculations must be attached on Page 3.</small>	
5. Wt. of Sling/Shackles	<input style="width: 100%;" type="text"/>	lbs	3. High Voltage or Electrical Hazards? <input style="width: 100%;" type="text"/> YES / NO	
6. Wt. of Jib/Ext. (erected/stowed)	<input style="width: 100%;" type="text"/>	lbs	<small>Note: If Electrical Hazards are present they must be shown on Page 4.</small>	
7. Wt. of Hoist Rope	<input style="width: 100%;" type="text"/>	lbs	4. Obstructions to Lift or Swing? <input style="width: 100%;" type="text"/> YES / NO	
8. Other:	<input style="width: 100%;" type="text"/>	lbs	<small>Note: If Obstructions are present they must be shown on Page 4.</small>	
TOTAL WEIGHT		<input style="width: 100%;" type="text"/>	5. Travel with Load Required? <input style="width: 100%;" type="text"/> YES / NO	
<small>Note: Source of load weight (Drawings, Calcs, etc.) must be attached on Page 2.</small>				
B. CRANE		F. OPERATOR QUALIFICATIONS		
1. Type of Crane	<u>Mobile Hydraulic Truck</u>		1. Certified Operator? <input style="width: 100%;" type="text"/> YES / NO	
2. Maximum Crane Capacity	<input style="width: 100%;" type="text"/>	lbs.	2. Option? <input style="width: 100%;" type="text"/>	
3. Radius (Maximum)	<input style="width: 100%;" type="text"/>	ft.	3. Certified for Type, Class & Capacity? <input style="width: 100%;" type="text"/> YES / NO	
4. Radius (Minimum)	<input style="width: 100%;" type="text"/>	ft.	4. Designated in writing by employer: <input style="width: 100%;" type="text"/> YES / NO	
5. Boom Length (Maximum)	<input style="width: 100%;" type="text"/>	ft.	G. PRE-LIFT CHECKLIST	
6. Boom Length (Minimum)	<input style="width: 100%;" type="text"/>	ft.	<small>(YES) N/A (NO)</small>	
7. Crane Capacity (Max Radius)	<input style="width: 100%;" type="text"/>	lbs.	1. Crane Inspected <input style="width: 100%;" type="text"/>	
8. Crane Capacity (Min Radius)	<input style="width: 100%;" type="text"/>	lbs.	2. Rigging Inspected <input style="width: 100%;" type="text"/>	
9. Boom Angle (Maximum)	<input style="width: 100%;" type="text"/>	deg.	3. Crane Set-up <input style="width: 100%;" type="text"/>	
10. Boom Angle (Minimum)	<input style="width: 100%;" type="text"/>	deg.	4. Overhead Hazard Check <input style="width: 100%;" type="text"/>	
11. Gross Load of Crane	<input style="width: 100%;" type="text"/>	lbs.	5. Swing Check <input style="width: 100%;" type="text"/>	
12. Lift is <input style="width: 100%;" type="text"/> % of the Crane's rated capacity			6. Counterweight Check <input style="width: 100%;" type="text"/>	
13. If Jib/Ext. is to be used:			7. Operator Qualifications <input style="width: 100%;" type="text"/>	
Length	<input style="width: 100%;" type="text"/>	ft.	8. Signal Person Qualifications <input style="width: 100%;" type="text"/>	
Offset	<input style="width: 100%;" type="text"/>	ft.	9. Rigger Qualifications <input style="width: 100%;" type="text"/>	
14. Rated Capacity of Jib/Ext.	<input style="width: 100%;" type="text"/>	lbs	10. Load Chart in Crane <input style="width: 100%;" type="text"/>	
C. HOIST ROPE		H. SIGNATURES		
1. # of Parts	<input style="width: 100%;" type="text"/>		1. Crane Operator <input style="width: 100%;" type="text"/>	
2. Rope Diameter	<input style="width: 100%;" type="text"/>		2. Rigger <input style="width: 100%;" type="text"/>	
3. Capacity	<input style="width: 100%;" type="text"/>		3. Signal Person <input style="width: 100%;" type="text"/>	
D. RIGGING				
1. Hitch Type(s)	<input style="width: 100%;" type="text"/>		4. Lift Supervisor <input style="width: 100%;" type="text"/>	
2. No. of Slings:	<input style="width: 100%;" type="text"/>	Size: <input style="width: 100%;" type="text"/>	5. Other <input style="width: 100%;" type="text"/>	
3. Sling Type:	<input style="width: 100%;" type="text"/>		6. Other <input style="width: 100%;" type="text"/>	
4. Sling Assembly Capacity:	<input style="width: 100%;" type="text"/>	lbs.		
5. Shackle Size(s):	<input style="width: 100%;" type="text"/>			
6. Shackle Rated Capacity(s)	<input style="width: 100%;" type="text"/>			

<div>Form 16-3</div> <div>CRITICAL LIFT PLAN</div> <div style="font-size: small;">For use of this form, see EM 385-1-1, Section 16. Proponent agency is Crane HHWG.</div>	
LOAD CALCULATIONS	
<i>Show here or attach calculations, drawings, etc.</i>	

LOCK OUT / TAG OUT CHECKLIST**2020 | Layton Construction Company LLC**
LOCKOUT / TAGOUT CHECKLIST

Name of Contractor(s):	Scope of Work: <input type="checkbox"/> Temporary Electrical Service <input type="checkbox"/> Permanent Electrical Service <input type="checkbox"/> Mechanical Work <input type="checkbox"/> Other _____
Name of Contractor's On Site Supervisor :	
Date of Coordination Meeting:	Date(s) LO/TO Will Be In Affect:

Electrical hazards and many forms of stored energy are unique in that there are very few properties that warn of their presence. **The goal of this Checklist is to minimize exposures with electrical equipment and other deadly hazards associated with stored energy.**

This Checklist shall be used to identify and/or review the following:

- ✓ Identify circumstances and/or locations where electrical hot work or other hazards **cannot be avoided**, and
- ✓ Identify the procedures and safety precautions that will be followed.

The contents of this Checklist shall be reviewed with all affected contractor employees and Layton Construction personnel.

Printed Name of Meeting Attendees:	Title/Responsibility:

- Does the Owner or host employer have a LO/TO Permit or LO/TO requirements? YES NO
- Has a project specific safety plan or Job Hazard Analysis (JHA) been developed by the contractor(s) doing the work? YES NO
- What type of energy sources or systems will be worked on and/or need to be isolated and locked out (Check all that apply)

Type of System	LO/TO Required? (Check One)		
	YES	NO	N/A
▪ Electrical			
▪ High volt (> 480 v)			
▪ Low volt (< 480 v)			
▪ Mechanical			
▪ Hydraulic/Steam			
▪ Pneumatic			
▪ Chemical			
▪ Other			

- Are other contractors or entities affected by this lock out? If yes, please identify: YES NO

LOCKOUT / TAGOUT CHECKLIST pg. 2

5. Identify the companies and individuals who are responsible for leading the Lockout-Tagout program for their employer. These individuals must be on site for the duration of the lockout-tagout in most circumstances.

Name of Contractor	Name of Individual

Safety Equipment and Procedures Checklist

- A. Will the work proceed in a flammable or Class I atmosphere? YES NO
If no, continue to item B. If Yes, check all safety equipment that will be used.

- ☐ Non sparking tools
☐ Intrinsically safe lights, tools, radios, etc.
☐ Non static charging clothing or shoes
☐ LEL Monitor

- B. Will other trades be working in the immediate vicinity of live circuits or otherwise be affected or exposed to the hazards of the activity? YES NO

If Yes, describe safety precautions that must be taken to protect affected workers:

- C. Check the safety equipment or procedures that will be followed to protect the safety of the workers conducting live work.

<input type="checkbox"/> Safety glasses with side shields and/or face shield	<input type="checkbox"/> Electrical blankets	<input type="checkbox"/> Gloves (electrical, hot work, or chemical resistant?)
<input type="checkbox"/> Hard hat (regular or high volt?)	<input type="checkbox"/> Blankets for hot work	<input type="checkbox"/> Insulating mats
<input type="checkbox"/> Leathers or heat resistant clothing	<input type="checkbox"/> Chemical resistant clothing	<input type="checkbox"/> Barricades around the work area
<input type="checkbox"/> Insulating tools	<input type="checkbox"/> Air monitor	<input type="checkbox"/> Retrieval equipment
<input type="checkbox"/> Low volt lighting	<input type="checkbox"/> Harness and lanyard	<input type="checkbox"/> Locks and Tags
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Comments: _____

- D. **To be completed by the employer(s) completing the work:** If work is to proceed on live, energized, charged, or otherwise operating systems, describe why work CANNOT proceed in a locked-out or de-energized state:

MONTHLY INSPECTION COLOR CODES SIGN


MONTHLY INSPECTION COLOR CODES

JAN & JUL = Yellow



FEB & AUG = White



MAR & SEPT = Brown



APR & OCT = Green



MAY & NOV = Red



JUN & DEC = Blue



Monthly focused inspections on extension cords, tool cords, ladders, etc. will be required. Each tool will be marked with colored tape designating the month of inspection. Inspections shall be performed by a competent person. Monthly focused inspections do not take the place of daily pre-use inspections.

NOTICE TO COMMENCE STEEL ERECTION

2020 / Layton Construction Company LLC
NOTICE TO COMMENCE STEEL ERECTION

PROJECT NAME: _____ PROJECT #: _____

Steel Erector Subcontractor:
Contact Name:
Address:

Layton Construction is hereby authorizing you to commence steel erection activities with the following notifications:

Concrete in footings, piers, and walls, and mortar in masonry piers and walls has attained, based on the appropriate ASTM standard test for field cured samples either 75% of the intended minimum compressive strength or sufficient strength to support the loads imposed during steel erection.	Name of testing agency: Attached testing reports:
Repairs or modifications were made to anchor rods/bolts: <input type="checkbox"/> Yes <input type="checkbox"/> No	Approval by: (Structural Engineer of Record): Approval in writing? <input type="checkbox"/> Yes <input type="checkbox"/> No (attach) Date approved:
Locations of repairs/modifications:	As built drawings available? <input type="checkbox"/> Yes <input type="checkbox"/> No

You are notified of your responsibility to: (Initial each)

Indicate to Layton Construction what material lay down areas are needed, and intended routes of transferring materials. Only those designated lay down areas will be utilized, and Layton Construction responsibility to maintain lay down areas will be limited to those that are designated.	Initials:
Preplan all overhead hoisting operations to prevent traveling loads over other contractor personnel, and to coordinate hoisting activities with Layton Construction and other contractors to minimize impacts on other operations.	
Provide a written site-specific erection plan if any part of your operations will deviate from the published OSHA Standard 29 CFR 1926.752(e).	
Conduct documented daily inspections of all cranes, forklifts, and other hoisting equipment utilized in steel erection activities.	
Designate a qualified trained rigger(s) to inspect all rigging equipment (Submit record of training) Name of qualified rigger:	
Maintain on the project written proof of training for all employees engaged in connecting, bolt-up, multiple lift rigging procedures, exposure to falls, equipment operation, and as required by any other specific standard.	
Assure that all columns are properly anchored by a minimum of 4 anchor bolts.	
Maintain and require the use of fall protection equipment for all employees exposed to fall elevations of 6 feet or greater as directed in the project Incident Prevention Program.	
Properly install perimeter guardrail systems on all exterior and interior leading edges consisting of a top rail and mid rail meeting the requirements of 29 CFR 1926.502 (b)(1-15)	
Maintain required fire protection/prevention equipment appropriate to the type of work operation and hazards involved.	
Meet all other requirements of the Layton Construction Incident Prevention Program, Published OSHA Standards, and the requirements of local regulations.	

Layton Construction Project Manager/Superintendent

Steel Erector Subcontractor



LAYTONCONSTRUCTION.COM



PRE-MOBILIZATION MEETING AGENDA*2020 | Layton Construction Company LLC***PRE-MOBILIZATION MEETING**

To: *Subcontractor Name*

From:

Subject: Preparation for the Pre-Mobilization Meeting

Date: *today's date*

The purpose of this memorandum is to help you prepare for the upcoming pre-mobilization meeting. By now you have been provided the site-specific safety plan for this project which identifies our expectations and your obligations regarding safety at this project. Our goal is to work with you to ensure that processes and procedures are in place such that everyone goes home safe to their family every day. Attached to this memorandum is a checklist for your review as you prepare for this meeting.

General Information

Please be prepared to identify your person(s) designated to be responsible for safety and quality including their qualifications. Please review and be prepared to discuss any required submittals and that you are aware of inspection requirements. Layton Construction requires that you have an iPad or IOS device insofar that we will be using BIM 360 Field to record inspections and safety observations.

If you will NOT be self-performing the assigned scope of work please be prepared to identify your subcontractors AND provide assurance that they are prepared to comply with the site-specific safety plan and requisite inspections.

In most cases the safety requirements of Layton Construction parallel those of OSHA. The primary variance is the required use of BIM 360 Field. If you are not comfortable with this technology, please reach out to us and we will provide the requisite training and support.

Task Specific Information

The attached checklist has several items that are not pertinent to every subcontractor. Please review and ensure you are prepared for those items specific to your anticipated scope of work. Please be prepared to discuss your safety management plan. Specific items may include:

1. Training records for all employees designated as the "competent person".
2. PPE assessment for tasks as required by OSHA.
3. General required training that has been accomplished:
 - a. Fall Protection
 - b. Confined Space
 - c. Hazardous Communication
 - d. Working with mobile elevated work platforms (MEWP)
 - e. Crane operator, rigger, signal person
 - f. OSHA 10 and/or OSHA 30

Summary

Please note that the intent of this meeting and effort is to ensure that we are well aligned with regard to risk identification and mitigation. At Layton Construction we do not assume that we have all the answers with regard to providing an injury free workplace. However, we are confident that through meaningful collaboration, clear expectations, and a commitment to safety we can in fact eliminate injuries to our valued employees.



LAYTONCONSTRUCTION.COM



BACK

SCAFFOLD INSPECTION

Front

[illegible]

[Back](#)

KEY RESPONSIBILITIES:

Competent Person: _____

Company: _____

Phone: _____

- Construct, modify and inspect as appropriate with respect to OSHA 29CFR 1910.282, 1926.451.
- Inspect scaffold for visible defects as specified on this card.
- Toe boards are required or barricades must be placed below.
- Has the scaffolding been inspected (as indicated on this card)?
- Is fall arrest/protection equipment required (as indicated on this card)?
- Is the area below the scaffold barricaded and debris nets installed (if necessary)?
- Have any conditions changed that could impact the structural integrity of this scaffolding since the last inspection? (Example: high winds, large amount of precipitation, physical damage). If so, contact the Competent Person (above) for inspection/repairs.

Trained User:

- Have completed the scaffold safety training course conducted by a qualified person.
- Completed a PTP, follow all safe work practices, and use proper PPE associated with the scaffolding.

Front

ATTENTION
THIS SCAFFOLD
WAS BUILT TO
MEET SAFETY
REGULATIONS
IT IS SAFE
TO USE

SIGNED
BY _____

DATE _____

SEE OTHER SIDE

INSPECTION

[illegible]

SILICA – TABLE 1

TABLE 1: SPECIFIED EXPOSURE CONTROL METHODS WHEN WORKING WITH MATERIALS CONTAINING CRYSTALLINE SILICA

Equipment/Task	Engineering and Work Practice Control Methods	Required Respiratory Protection and Minimum Assigned Protection Factor (APF)	
		≤ 4 hours / shift	> 4 hours / shift
(iv) Walk-behind saws	Use saw equipped with integrated water delivery system that continuously feeds water to the blade. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions. <ul style="list-style-type: none"> When used outdoors When used indoors or in an enclosed area 	None APF 10	None APF 10
(v) Drivable saws	For tasks performed outdoors only: <ul style="list-style-type: none"> Use saw equipped with integrated water delivery system that continuously feeds water to the blade. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions 	None	None
(vi) Rig-mounted core saws or drills	Use tool equipped with integrated water delivery system that supplies water to cutting surface. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions.	None	None
(vii) Handheld and stand-mounted drills (including impact and rotary hammer drills)	Use drill equipped with commercially available shroud or cowl with dust collection system. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions. Dust collector must provide the air flow recommended by the tool manufacturer, or greater, and have a filter with 99% or greater efficiency and a filter-cleaning mechanism. Use a HEPA-filtered vacuum when cleaning holes.	None	None
(viii) Dowell drilling rigs for concrete	For tasks performed outdoors only: <ul style="list-style-type: none"> Use shroud around drill bit with a dust collection system. Dust collector must have a filter with 99% or greater efficiency and a filter-cleaning mechanism. Use a HEPA-filtered vacuum when cleaning holes 	APF 10	APF 10
(ix) Vehicle-mounted drilling rigs for rock and concrete	Use dust collection system with close capture hood or shroud around drill bit with a low-flow water spray to wet the dust at the discharge point from the dust collector	None	None
	OR Operate from within an enclosed cab and use water for dust suppression on drill bit.	None	None
(x) Jackhammers and handheld powered chipping tools	Use tools with water delivery system that supplies a continuous stream or spray of water at the point of impact. <ul style="list-style-type: none"> When used outdoors When used indoors or in an enclosed area 	None APF 10	None APF 10
	OR Use tool equipped with commercially available shroud and dust collection system. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions. Dust collector must provide the air flow recommended by the tool manufacturer, or greater, and have a filter with 99% or greater efficiency and a filter-cleaning mechanism. <ul style="list-style-type: none"> When used outdoors When used indoors or in an enclosed area 	None APF 10	None APF 10
(xi) Handheld grinders for mortar removal (i.e. tuckpointing)	Use grinder equipped with commercially available shroud and dust collection system. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions. Dust collector must provide 25 cubic feet per minute (cfm) or greater of airflow per inch of wheel diameter and have a filter with 99% or greater efficiency and a cyclonic pre-separator or filter-cleaning mechanism.	APF 10	APF 10
(xii) Handheld grinders for uses other than mortar removal	For tasks performed outdoors only: Use grinder equipped with integrated water delivery system that continuously feeds water to the grinding surface. Operate and maintain	None	None

APPENDIX 16

Equipment/Task	Engineering and Work Practice Control Methods	Required Respiratory Protection and Minimum Assigned Protection Factor (APF)	
		≤ 4 hours / shift	> 4 hours / shift
	<p>tool in accordance with manufacturer's instructions to minimize dust emissions.</p> <p>OR</p> <p>Use grinder equipped with commercially available shroud and dust collection system. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions. Dust collector must provide 25 cubic feet per minute (cfm) or greater of airflow per inch of wheel diameter and have a filter with 99% or greater efficiency and a cyclonic pre-separator or filter-cleaning mechanism.</p> <ul style="list-style-type: none"> When used outdoors When used in an enclosed area 	None	APF 10
(xiii) Walk-behind milling machines and floor grinders	<p>Use machine equipped with integrated water delivery system that continuously feeds water to the cutting surface. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions.</p> <p>OR</p> <p>Use machine equipped with dust collection system recommended by the manufacturer. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions. Dust collector must provide the air flow recommended by the manufacturer, or greater, and have a filter with 99% or greater efficiency and a filter-cleaning mechanism. When used indoors or in an enclosed area, use a HEPA-filtered vacuum to remove loose dust in between passes.</p>	None	None
(xiv) Small drivable milling machines (less than half-lane)	Use a machine equipped with supplemental water sprays designed to suppress dust. Water must be combined with a surfactant. Operate and maintain machine to minimize dust emissions.	None	None
(xv) Large drivable milling machines (half-lane and larger)	<p>For cuts of any depth on asphalt only:</p> <p>Use machine equipped with exhaust ventilation on drum enclosure and supplemental water sprays designed to suppress dust. Operate and maintain machine to minimize dust emissions. For cuts of four inches in depth or less on any substrate:</p> <ul style="list-style-type: none"> Use machine equipped with exhaust ventilation on drum enclosure and supplemental water sprays designed to suppress dust. Operate and maintain machine to minimize dust emissions. 	None	None
	<p>OR</p> <p>Use a machine equipped with supplemental water spray designed to suppress dust. Water must be combined with a surfactant. Operate and maintain machine to minimize dust emissions.</p>	None	None
	Use equipment designed to deliver water spray or mist for dust suppression at crusher and other points where dust is generated (i.e., hoppers, conveyers, sieves/sizing or vibrating components, and discharge points). Operate and maintain machine in accordance with manufacturer's instructions to minimize dust emissions. Use a ventilated booth that provides fresh, climate-controlled air to the operator, or a remote control station.	None	None
(xvi) Crushing machines	Use equipment designed to deliver water spray or mist for dust suppression at crusher and other points where dust is generated (i.e., hoppers, conveyers, sieves/sizing or vibrating components, and discharge points). Operate and maintain machine in accordance with manufacturer's instructions to minimize dust emissions. Use a ventilated booth that provides fresh, climate-controlled air to the operator, or a remote control station.	None	None
(xvii) Heavy equipment and utility vehicles used to abrade or fracture silica-containing materials (i.e., hoe-ramming, rock ripping) or used during demolition activities involving silica-containing materials	Operate equipment from within an enclosed cab.	None	None
	When employees outside of the cab are engaged in the task, apply water and/or dust suppressants as necessary to minimize dust emissions	None	None
Equipment/Task	Engineering and Work Practice Control Methods	Required Respiratory Protection and Minimum Assigned Protection Factor (APF)	
		≤ 4 hours / shift	> 4 hours / shift
(xviii) Heavy equipment and utility vehicles for tasks such as grading and excavating but not including: Demolishing, abrading, or fracturing silica-containing materials	Apply water and/or dust suppressants as necessary to minimize dust emissions.	None	None
	<p>OR</p> <p>When the equipment operator is the only employee engaged in the task, operate equipment from within an enclosed cab.</p>	None	None

UTILITY PROTECTION PERMIT

2020 | Layton Construction Company LLC
UTILITY PROTECTION PERMIT

PROJECT NAME: _____ PROJECT #: _____

RESPONSIBLE SUBCONTRACTOR: _____

To be completed prior to any demo, rework, excavation, trenching, core drilling, or saw cutting work. Locator Services and AS BUILTS MUST BE VERIFIED AND CURRENT. **PRE-TASK PLAN MUST BE COMPLETED, REVIEWED, AND APPROVED BY LAYTON CONSTRUCTION SUPERINTENDENT PRIOR TO START OF WORK.**

Project:			Date:		
Scope of work:			Location:		
Competent Person:					
Utilities Identified (Power, Gas, Fibre Optic, Water, Etc.):		Size, KV, Material Type:		Location:	
Utilities				YES	NO
Utility location verified by as builts, grid lines, drawings, and private locator. Attach verification.					
Locator Service Number:		Locator Effective Date:		Locator Expiration Date:	
Locations of utilities marked and markings sustainable for duration of work. Describe.					
Utilities are protected, supported and hard barriers are installed as needed. (Explain)					
All utilities will be potholed at a minimum every 200 feet horizontally for exterior work, "openfield", or more often if locating services or as builts identify need. Interior potholing every 25'.					
Hand digging or soft excavation (pressurized water or compressed air) will be used to expose utilities (daylighting) for locations prior to excavation or penetration, and when any excavation or surface penetration are within 24" of utilities. Explain process to be used, and location.					
Selective or soft demo will be used to discover in-wall, above-ceiling, and in or below concrete slab utilities. Explain process to be used and location.					
Map of existing utilities current and posted in affected area.					
Barriers installed to prevent unauthorized personnel to access area.					
Detailed Pre-Task Plan completed, reviewed by crews and Layton Superintendent.					
On existing facilities, contingency plans in case of utility disruption have been developed and shared with owner, Layton Construction team, and integrated into the site emergency response plan. (Attach plan)					

Subcontractor Supervisor
Competent Person(s):
Owner's Representative:

Layton Project Superintendent: _____
 Signature: _____ Date: _____

Employees working in area. (Print Names)		



LAYTONCONSTRUCTION.COM



NOTICE OF NON-COMPLIANCE**2020 / Layton Construction Company LLC
NOTICE OF NON-COMPLIANCE**

PROJECT NAME: _____ PROJECT #: _____

Subcontractor Name: _____ Date: _____

Subcontractor is out of compliance with

- ☐ Violation of Federal or State Standards
- ☐ Violation of Layton Companies / Owner Requirements
- ☐ Violation of Contractors' Safety Rules / Policy

Date: _____ Time: _____

Location of Violation: _____

Actions / Conditions Observed: _____

Violations must be corrected by Date: _____ Time: _____

_____ Date: _____ Time: _____

Signature of person issuing notice

Contractor must list corrective actions taken to bring his/her area into compliance: _____

Were corrective actions made IMMEDIATELY or DELAYED ☐ Yes ☐ No

If DELAYED, explain the reason for the delay in making corrections: _____

Print Name of person making corrections: _____ Date / Time: _____

_____ Date: _____ Time: _____

Signature of Subcontractor Safety Representative



LAYTONCONSTRUCTION.COM

